

SUMMARY OF QUANTITIES					100% STATE		0700L		07POL	
CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	TRAFFIC SIGNALS	STRUCTURES	80% STATE 20% LILY LAKE SIDEWALK	100% ELBURN & COUNTRYSIDE FPD		
			<i>URBAN</i>	0004	0021	<i>0008</i>	0021	0021		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNITS	58	58						
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNITS	60	60						
20100500	TREE REMOVAL, ACRES	ACRE	0.8	0.8						
20101000	TEMPORARY FENCE	FOOT	2,160	2,160						
20101100	TREE TRUNK PROTECTION	EACH	2	2						
20101200	TREE ROOT PRUNING	EACH	2	2						
20200100	EARTH EXCAVATION	CU YD	8,338	8,338						
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	29,182	29,182						
20400800	FURNISHED EXCAVATION	CU YD	16,003	16,003						
20700110	POROUS GRANULAR EMBANKMENT	CU YD	22,596	22,596						
20800150	TRENCH BACKFILL	CU YD	738	738						
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1,428	1,428						
21101615	TOPSOIL FURNISH AND PLACE, 4 INCH	SQ YD	7,703	7,703						
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	<i>7,362</i>	<i>7,362</i>						
25000210	SEEDING, CLASS 2A	ACRE	1.3	1.3						
25000310	SEEDING, CLASS 4	ACRE	<i>1.5</i>	<i>1.5</i>						
25000320	SEEDING, CLASS 5	ACRE	0.5	0.5						
25003310	INTERSEEDING, CLASS 4	ACRE	0.6	0.6						
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	<i>272</i>	<i>272</i>						
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	<i>272</i>	<i>272</i>						
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	<i>272</i>	<i>272</i>						
25100115	MULCH, METHOD 2	ACRE	0.7	0.7						
25100630	EROSION CONTROL BLANKET	SQ YD	6,069	6,069						
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	<i>4,016</i>	<i>4,016</i>						
25100900	TURF REINFORCEMENT MAT	SQ YD	116	116						
25200110	SODDING, SALT TOLERANT	SQ YD	1,463	1,463						
25200200	SUPPLEMENTAL WATERING	UNIT	23	23						
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,800	1,800						
28000305	TEMPORARY DITCH CHECKS	FOOT	310	310						
28000510	INLET FILTERS	EACH	61	61						
28000400	PERIMETER EROSION BARRIER	FOOT	6,016	6,016						
28100107	STONE RIPRAP, CLASS A4	SQ YD	155	155						
28200200	FILTER FABRIC	SQ YD	155	155						
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	155	155						
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SQ YD	21,126	21,126						
35300410	PORTLAND CEMENT CONCRETE BASE COURSE 9 1/2"	SQ YD	428	428						
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	30	30						
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	880	880						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2	2						
40600300	AGGREGATE (PRIME COAT)	TON	9	9						
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	233	233						
40600895	CONSTRUCTING TEST STRIP	EACH	2	2						

\* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = .USER.	DESIGNED - AR	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL 64 AT IL 47 INTERSECTION IMPROVEMENTS SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
*FILEL*		DRAWN - AR	REVISED -			307	126N-1	KANE	156	4	
	PLOT SCALE = 50,000 Ft / IN.	CHECKED - RS	REVISED -			SCALE:		SHEET NO. 1 OF 5 SHEETS		STA. TO STA.	
	PLOT DATE = 9/2/2011	DATE - 09-01-2011	REVISED -			ILLINOIS FED. AID PROJECT CONTRACT NO. 62278					