

SUMMARY OF QUANTITIES					100% STATE			07COL	07POL
CODE NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	TRAFFIC SIGNALS	STRUCTURES	80% STATE 20% LILY LAKE SIDEWALK	100% ELBURN & COUNTRYSIDE FPD	
			<i>URBAN</i>	0004	0021	0008	0021	0021	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6,408	6,408					
* 72000100	SIGN PANEL - TYPE 1	SQ FT	316	286	30				
* 72000200	SIGN PANEL - TYPE 2	SQ FT	89	89					
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	664	664					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	237	237					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,070	1,070					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	70	70					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	21	21					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	42	42					
* 78008300	<i>POLYUREA</i> PAVEMENT MARKING - LETTERS & SYMBOLS <i>TYPE II</i>	SQ FT	296	296					
* 78008310	<i>POLYUREA</i> PAVEMENT MARKING - LINE 4" <i>TYPE II</i>	FOOT	12,855	12,855					
* 78008330	<i>POLYUREA</i> PAVEMENT MARKING - LINE 8" <i>TYPE II</i>	FOOT	1,977	1,977					
* 78008340	<i>POLYUREA</i> PAVEMENT MARKING - LINE 8" <i>TYPE II</i>	FOOT	1,108	1,108					
* 78008350	<i>POLYUREA</i> PAVEMENT MARKING - LINE 12" <i>TYPE II</i>	FOOT	737	737					
* 78008370	<i>POLYUREA</i> PAVEMENT MARKING - LINE 24" <i>TYPE II</i>	FOOT	160	160					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	178	178					
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	20	20					
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	12	12					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	216	216					
* 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1				
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	824		824				
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	185		185				
* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	49		49				
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	226		226				
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	619		619				
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	361		361				
* 81400100	HANDHOLE	EACH	8		8				
* 81400200	HEAVY-DUTY HANDHOLE	EACH	5		5				
* 81400300	DOUBLE HANDHOLE	EACH	2		2				
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,246		1,246				
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1				
* 86200300	UNINTERRUPTIBLE POWER SUPPLY, EXTENDED	EACH	1		1				
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,677		1,677				
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2,293		2,014			279	
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	268		268				
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	3,094		3,094				
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2,819		2,819				
* 87301800	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 4 2 C	FOOT	320		320				
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1 C	FOOT	1,702		1,702				
* 87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	2		2				
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2		2				
* 87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	2		2				
* 81009300	CONDUIT IN TRENCH, 3 1/2" DIA., GALVANIZED STEEL	FOOT	12		12				

* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = USER	DESIGNED - AR	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 64 AT IL 47 INTERSECTION IMPROVEMENTS SUMMARY OF QUANTITIES	F.A.P. RTE. 307	SECTION 126N-1	COUNTY KANE	TOTAL SHEETS 156	SHEET NO. 7	Rev.	
#FILE#	PLOT SCALE = 50,000 ft / IN.	DRAWN - AR	REVISED -			SCALE:	SHEET NO. 4 OF 5 SHEETS	STA.	TO STA.	CONTRACT NO. 62278		ILLINOIS FED. AID PROJECT
	PLOT DATE = 9/1/2011	CHECKED - RS	REVISED -									
		DATE - 09-01-2011	REVISED -									