

Specialty Item	Special Provision	Item No	Description	Unit	Construction Code 0028 Quantity	Construction Code 0042 Quantity
		20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	105	
		20101200	TREE ROOT PRUNING	EACH	17	
		20200100	EARTH EXCAVATION	CU YD	2881	
		20800150	TRENCH BACKFILL	CU YD	362	
		21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	8684	
		21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	6352	
		25000400	NITROGEN FERTILIZER NUTRIENT	POUND	131	
		25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	131	
		25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	131	
		25200110	SODDING, SALT TOLERANT	SQ YD	7030	
		25200200	SUPPLEMENTAL WATERING	UNIT	35	
		28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	200	
		28000400	PERIMETER EROSION BARRIER	FOOT	6030	
		28000500	INLET AND PIPE PROTECTION	EACH	10	
		28000510	INLET FILTERS	EACH	17	
		31101180	SUB-BASE GRANULAR MATERIAL, TYPE B 2"	SQ YD	575	
		31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1649	
		35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	7035	
		35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	1443	
		40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2	
		40600300	AGGREGATE (PRIME COAT)	TON	1	
		40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	29	
		40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	894	
		40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1385	
		42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	5996	
	SP	42400800	DETECTABLE WARNINGS	SQ FT	248	
		44000100	PAVEMENT REMOVAL	SQ YD	1010	
		44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	235	
		44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	513	
	SP	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	174	
		44000600	SIDEWALK REMOVAL	SQ FT	17142	
	SP	44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	20	
	SP	44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	40	
	SP	550B0320	STORM SEWERS, CLASS B, TYPE 2 8"	FOOT	803	
	SP	550B0340	STORM SEWERS, CLASS B, TYPE 2 12"	FOOT	280	
		60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	
		60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	
		60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	11	
		60250200	CATCH BASINS TO BE ADJUSTED	EACH	6	
		60255500	MANHOLES TO BE ADJUSTED	EACH	7	
		60260100	INLETS TO BE ADJUSTED	EACH	1	
	SP	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1093	
		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	
		67100100	MOBILIZATION	L SUM	1	
		70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	
		70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	
		70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	
		70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	

Specialty Item	Special Provision	Item No	Description	Unit	Construction Code 0028 Quantity	Construction Code 0042 Quantity
		72000100	SIGN PANEL - TYPE 1	SQ FT	181	
		72400100	REMOVE SIGN PANEL ASSEMBLY-TYPE A	EACH	44	
		72400310	REMOVE SIGN PANEL-TYPE 1	SQ FT	24	
		72900100	METAL POST - TYPE A	FOOT	385	
*		78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	310	
*		78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4704	
*		78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1053	
*		78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	180	
*		78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	183	
*		78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	20	
*		81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	37	
*		81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	37	
*	SP	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	
*		87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1416	
*		87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1018	
*		87601200	PEDESTRIAN PUSH-BUTTON POST, GALVANIZED STEEL, TYPE II	EACH	6	
*		87900200	DRILL EXISTING HANDHOLE	EACH	6	
*		88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8	
*		88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2	
*		88800100	PEDESTRIAN PUSH-BUTTON	EACH	16	
*		89500200	RELOCATE EXISTING PEDESTRIAN SIGNAL HEAD	EACH	2	
*		89502200	MODIFY EXISTING CONTROLLER	EACH	2	
*		89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	435	
*		89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	111	
*	SP	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2	
*		A2000120	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	6	
*		A2006420	TREE, QUERCUS ALBA (WHITE OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	6	
	SP	X0328852	RADAR SPEED SIGN	EACH	1	
		X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	5	
	SP	X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1	
	SP	X8140115	HANDHOLE TO BE ADJUSTED	EACH	3	
	SP	Z0004510	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"	SQ YD	229	
	SP	Z0004544	HOT-MIX ASPHALT DRIVEWAY PAVEMENT REMOVAL	SQ YD	229	
	SP	Z0023202	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	17	
	SP	Z0043500	PRECAST CONCRETE CAR BUMPER	EACH	10	
	SP	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	
	SP	Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	80	
	SP	XX000882	WOOD FENCE	FOOT	270	
	SP	XX003313	REMOVE AND REINSTALL BRICK PAVER	SQ FT	36	
	SP	XX003424	CONNECTION TO EXISTING STRUCTURE	EACH	5	
	SP	XZ176100	REMOVE AND RESET BUMPER BLOCKS	EACH	121	
	SP	XZ177600	REMOVE EXISTING BUMPER BLOCKS	EACH	10	
	SP	44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	6144	

FILE NAME VILLAGE WIDE BIKE PATH - STAGE 2  
 FAU RTE. 1459 (26TH STREET), FAU 2759  
 (DESPLAINES AVENUE), VILLAGE COMMONS,  
 HAINSWORTH AVENUE, 25TH STREET AND VETERANS  
 PARK FROM FORESTVIEW AVENUE TO VETERAN DRIVE  
 #09296

USER NAME =  
 PLOT SCALE = NONE  
 PLOT DATE =

DESIGNED -- THK  
 DRAWN -- JFP-JEP  
 CHECKED -- THK  
 DATE -- 1-29-10

REVISED -- THK 3-09-10  
 REVISED -- THK 4-06-10  
 REVISED -- TRB 8-29-11  
 REVISED --

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

Frank Novotny & Associates, Inc.  
 835 Midway Drive • Willmetts, IL • 60091 • Telephone: (815) 837-8840 • Fax: (815) 837-0132  
 ILLINOIS PROFESSIONAL DESIGN FIRM NO. 184-000638

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	06-00080-01-BT	COOK	37	3
CONTRACT NO. 63461				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT HPP-3463(006)				