

| EARTH EXCAVATION QUANTITIES (CUT / FILL) | | | | | | | | | | |
|--|-----------------|------|----------|------------------------|------|---------------------|-------|----------------------|--------|------------------------|
| 26th STREET - 9TH AVENUE TO 1ST AVENUE | | | | | | | | | | |
| SECTION STATIONS X 100 | END AREAS, S.F. | | DISTANCE | SUM OF END AREAS, S.F. | | AVE END AREAS, S.F. | | SECTION TOTALS, C.Y. | | SECTION STATIONS X 100 |
| | CUT | FILL | | CUT | FILL | CUT | FILL | CUT | FILL | |
| 1.30 | 10.18 | 0.00 | | | | | | | | 1.30 |
| 1.65 | 10.97 | 0.00 | 35 | 21.15 | 0 | 10.575 | 0 | 13.71 | 0.00 | 1.65 |
| 2.00 | 5.80 | 0.02 | 35 | 16.77 | 0.02 | 8.385 | 0.01 | 10.87 | 0.01 | 2.00 |
| 3.00 | 6.37 | 0.02 | 100 | 12.17 | 0.04 | 6.085 | 0.02 | 22.54 | 0.07 | 3.00 |
| 4.00 | 5.20 | 0.12 | 100 | 11.57 | 0.14 | 5.785 | 0.07 | 21.43 | 0.26 | 4.00 |
| 5.00 | 3.64 | 0.37 | 100 | 8.24 | 0.49 | 4.12 | 0.245 | 15.26 | 0.91 | 5.00 |
| 6.00 | 6.27 | 0.02 | 100 | 9.31 | 0.39 | 4.655 | 0.195 | 17.24 | 0.72 | 6.00 |
| 7.00 | 6.23 | 0.04 | 100 | 12.5 | 0.08 | 6.25 | 0.03 | 23.16 | 0.11 | 7.00 |
| 8.00 | 7.12 | 0.00 | 100 | 13.35 | 0.04 | 6.675 | 0.02 | 24.72 | 0.07 | 8.00 |
| 9.00 | 8.75 | 0.00 | 100 | 15.87 | 0 | 7.935 | 0 | 29.39 | 0.00 | 9.00 |
| 10.00 | 8.07 | 0.00 | 100 | 16.82 | 0 | 8.41 | 0 | 31.15 | 0.00 | 10.00 |
| 11.00 | 6.99 | 0.00 | 100 | 15.06 | 0 | 7.53 | 0 | 27.89 | 0.00 | 11.00 |
| 12.00 | 7.99 | 0.00 | 100 | 14.98 | 0 | 7.49 | 0 | 27.74 | 0.00 | 12.00 |
| 13.00 | 4.05 | 0.21 | 100 | 12.04 | 0.21 | 6.02 | 0.105 | 22.30 | 0.39 | 13.00 |
| 14.00 | 5.91 | 0.04 | 100 | 9.96 | 0.25 | 4.98 | 0.125 | 18.44 | 0.46 | 14.00 |
| 15.00 | 4.63 | 0.09 | 100 | 10.54 | 0.13 | 5.27 | 0.065 | 19.52 | 0.24 | 15.00 |
| 16.00 | 7.12 | 0.00 | 100 | 11.75 | 0.09 | 5.875 | 0.045 | 21.76 | 0.17 | 16.00 |
| 17.00 | 8.49 | 0.00 | 100 | 15.61 | 0 | 7.805 | 0 | 28.91 | 0.00 | 17.00 |
| 18.00 | 6.43 | 0.00 | 100 | 14.92 | 0 | 7.46 | 0 | 27.63 | 0.00 | 18.00 |
| 19.00 | 7.27 | 0.00 | 100 | 13.7 | 0 | 6.85 | 0 | 25.37 | 0.00 | 19.00 |
| 20.00 | 7.96 | 0.00 | 100 | 15.23 | 0 | 7.615 | 0 | 28.20 | 0.00 | 20.00 |
| 21.00 | 6.69 | 0.01 | 100 | 14.65 | 0.01 | 7.325 | 0.005 | 27.13 | 0.02 | 21.00 |
| 22.00 | 7.88 | 0.00 | 100 | 14.57 | 0.01 | 7.285 | 0.005 | 26.98 | 0.02 | 22.00 |
| 23.00 | 7.60 | 0.00 | 100 | 15.48 | 0 | 7.74 | 0 | 28.67 | 0.00 | 23.00 |
| 24.00 | 7.62 | 0.00 | 100 | 15.22 | 0 | 7.61 | 0 | 28.19 | 0.00 | 24.00 |
| 25.00 | 5.82 | 0.08 | 100 | 13.44 | 0.08 | 6.72 | 0.04 | 24.89 | 0.15 | 25.00 |
| 26.00 | 7.73 | 0.00 | 100 | 13.55 | 0.08 | 6.775 | 0.04 | 25.09 | 0.15 | 26.00 |
| 27.00 | 9.06 | 0.00 | 100 | 16.79 | 0 | 8.395 | 0 | 31.09 | 0.00 | 27.00 |
| 27.50 | 9.83 | 0.00 | 50 | 18.89 | 0 | 9.445 | 0 | 17.49 | 0.00 | 27.50 |
| TOTAL GROSS VOLUMES THIS PAGE | | | | | | | | | 666.74 | 3.75 |

| EARTH EXCAVATION QUANTITIES (CUT / FILL) | | | | | | | | | | |
|--|-----------------|------|----------|------------------------|------|---------------------|-------|----------------------|--------|------------------------|
| VILLAGE COMMONS | | | | | | | | | | |
| SECTION STATIONS X 100 | END AREAS, S.F. | | DISTANCE | SUM OF END AREAS, S.F. | | AVE END AREAS, S.F. | | SECTION TOTALS, C.Y. | | SECTION STATIONS X 100 |
| | CUT | FILL | | CUT | FILL | CUT | FILL | CUT | FILL | |
| 65.31 | 12.40 | 0.00 | | | | | | | | 65.31 |
| 65.81 | 10.03 | 0.15 | 50 | 22.43 | 0.15 | 11.22 | 0.075 | 20.77 | 0.14 | 65.81 |
| 66.00 | 13.09 | 0.00 | 19 | 23.12 | 0.16 | 11.56 | 0.075 | 8.13 | 0.05 | 66.00 |
| 66.55 | 18.28 | 0.00 | 55 | 31.37 | 0 | 15.69 | 0 | 31.95 | 0.00 | 66.55 |
| 66.71 | 16.50 | 0.00 | 16 | 34.78 | 0 | 17.39 | 0 | 10.31 | 0.00 | 66.71 |
| 67.50 | 13.63 | 0.00 | 79 | 30.13 | 0 | 15.07 | 0 | 44.08 | 0.00 | 67.50 |
| 68.06 | 23.49 | 0.00 | 56 | 37.12 | 0 | 18.56 | 0 | 38.49 | 0.00 | 68.06 |
| 68.56 | 21.64 | 0.00 | 50 | 45.13 | 0 | 22.57 | 0 | 41.79 | 0.00 | 68.56 |
| 69.00 | 38.02 | 0.00 | 44 | 59.66 | 0 | 29.89 | 0 | 48.61 | 0.00 | 69.00 |
| 69.50 | 44.49 | 0.00 | 50 | 82.51 | 0 | 41.26 | 0 | 76.40 | 0.00 | 69.50 |
| 70.00 | 4.61 | 0.14 | 50 | 49.1 | 0.14 | 24.55 | 0.07 | 45.46 | 0.13 | 70.00 |
| 70.50 | 10.80 | 0.00 | 50 | 15.41 | 0.14 | 7.71 | 0.07 | 14.27 | 0.13 | 70.50 |
| 71.00 | 9.89 | 0.00 | 50 | 20.69 | 0 | 10.35 | 0 | 19.16 | 0.00 | 71.00 |
| 71.48 | 11.77 | 0.00 | 48 | 21.66 | 0 | 10.83 | 0 | 19.25 | 0.00 | 71.48 |
| 71.92 | 11.79 | 0.00 | 44 | 23.66 | 0 | 11.78 | 0 | 19.20 | 0.00 | 71.92 |
| 73.88 | 8.76 | 0.00 | 196 | 20.55 | 0 | 10.28 | 0 | 74.59 | 0.00 | 73.88 |
| 74.85 | 18.20 | 0.00 | 97 | 23.96 | 0 | 11.98 | 0 | 43.04 | 0.00 | 74.85 |
| 75.80 | 16.74 | 0.00 | 95 | 31.94 | 0 | 15.97 | 0 | 56.19 | 0.00 | 75.80 |
| 76.82 | 10.94 | 0.00 | 102 | 27.68 | 0 | 13.84 | 0 | 52.28 | 0.00 | 76.82 |
| 77.77 | 9.83 | 0.00 | 95 | 20.77 | 0 | 10.39 | 0 | 36.54 | 0.00 | 77.77 |
| 78.70 | 14.13 | 0.00 | 93 | 23.96 | 0 | 11.98 | 0 | 41.26 | 0.00 | 78.70 |
| 79.70 | 10.85 | 0.00 | 100 | 24.98 | 0 | 12.49 | 0 | 46.26 | 0.00 | 79.70 |
| 81.18 | 11.47 | 0.00 | 148 | 22.32 | 0 | 11.16 | 0 | 61.17 | 0.00 | 81.18 |
| 82.13 | 12.52 | 0.00 | 95 | 23.99 | 0 | 12.00 | 0 | 42.20 | 0.00 | 82.13 |
| 83.14 | 10.04 | 0.00 | 101 | 22.66 | 0 | 11.28 | 0 | 42.20 | 0.00 | 83.14 |
| 84.14 | 9.26 | 0.00 | 100 | 19.3 | 0 | 9.65 | 0 | 39.74 | 0.00 | 84.14 |
| 84.78 | 13.43 | 0.00 | 64 | 22.69 | 0 | 11.35 | 0 | 26.89 | 0.00 | 84.78 |
| TOTAL GROSS VOLUMES THIS PAGE | | | | | | | | | 996.24 | 0.45 |

| EARTH EXCAVATION QUANTITIES (CUT / FILL) | | | | | | | | | | |
|--|-----------------|------|----------|------------------------|------|---------------------|------|----------------------|--------|------------------------|
| 25th STREET - PAVEMENT SECTIONS | | | | | | | | | | |
| SECTION STATIONS X 100 | END AREAS, S.F. | | DISTANCE | SUM OF END AREAS, S.F. | | AVE END AREAS, S.F. | | SECTION TOTALS, C.Y. | | SECTION STATIONS X 100 |
| | CUT | FILL | | CUT | FILL | CUT | FILL | CUT | FILL | |
| 90.81 | 34.46 | 0.00 | | | | | | | | 90.81 |
| 91.50 | 60.18 | 0.00 | 69 | 94.64 | 0 | 47.32 | 0 | 120.93 | 0.00 | 91.50 |
| 92.00 | 62.90 | 0.00 | 50 | 113.08 | 0 | 56.54 | 0 | 104.70 | 0.00 | 92.00 |
| 92.50 | 44.52 | 0.00 | 50 | 97.42 | 0 | 48.71 | 0 | 90.20 | 0.00 | 92.50 |
| 93.00 | 49.26 | 0.00 | 50 | 93.78 | 0 | 46.89 | 0 | 86.83 | 0.00 | 93.00 |
| 93.50 | 47.63 | 0.00 | 50 | 96.89 | 0 | 48.445 | 0 | 89.71 | 0.00 | 93.50 |
| 93.70 | 42.55 | 0.00 | 20 | 90.18 | 0 | 45.09 | 0 | 33.40 | 0.00 | 93.70 |
| 94.00 | 59.37 | 0.00 | 30 | 101.92 | 0 | 50.96 | 0 | 56.62 | 0.00 | 94.00 |
| 94.55 | 50.20 | 0.00 | 55 | 109.57 | 0 | 54.785 | 0 | 111.60 | 0.00 | 94.55 |
| 94.95 | 63.13 | 0.00 | 40 | 113.33 | 0 | 56.665 | 0 | 83.95 | 0.00 | 94.95 |
| 95.15 | 0.00 | 0.00 | 20 | 63.13 | 0 | 31.565 | 0 | 23.38 | 0.00 | 95.15 |
| TOTAL GROSS VOLUMES THIS PAGE | | | | | | | | | 777.95 | 0.00 |

| EARTH EXCAVATION QUANTITIES (CUT / FILL) | | | | | | | | | | |
|---|-----------------|------|----------|------------------------|------|---------------------|-------|----------------------|--------|------------------------|
| VETERANS PARK - 25TH STREET TO VETERANS DRIVE | | | | | | | | | | |
| SECTION STATIONS X 100 | END AREAS, S.F. | | DISTANCE | SUM OF END AREAS, S.F. | | AVE END AREAS, S.F. | | SECTION TOTALS, C.Y. | | SECTION STATIONS X 100 |
| | CUT | FILL | | CUT | FILL | CUT | FILL | CUT | FILL | |
| 96.00 | 8.72 | 0.00 | | | | | | | | 96.00 |
| 97.00 | 7.92 | 0.00 | 100 | 16.64 | 0 | 8.32 | 0 | 30.81 | 0.00 | 97.00 |
| 98.00 | 9.28 | 0.00 | 100 | 17.2 | 0 | 8.6 | 0 | 31.85 | 0.00 | 98.00 |
| 99.00 | 9.32 | 0.08 | 100 | 18.6 | 0.08 | 9.3 | 0.04 | 34.44 | 0.15 | 99.00 |
| 99.94 | 10.55 | 0.00 | 94 | 19.87 | 0.08 | 9.935 | 0.04 | 34.59 | 0.14 | 99.94 |
| 101.00 | 6.76 | 0.00 | 106 | 17.31 | 0 | 8.655 | 0 | 33.98 | 0.00 | 101.00 |
| 102.00 | 5.57 | 0.00 | 100 | 12.33 | 0 | 6.165 | 0 | 22.83 | 0.00 | 102.00 |
| 103.00 | 8.28 | 0.00 | 100 | 13.85 | 0 | 6.925 | 0 | 25.65 | 0.00 | 103.00 |
| 104.00 | 9.26 | 0.00 | 100 | 17.54 | 0 | 8.77 | 0 | 32.48 | 0.00 | 104.00 |
| 105.00 | 9.96 | 0.00 | 100 | 19.22 | 0 | 9.61 | 0 | 35.59 | 0.00 | 105.00 |
| 106.00 | 6.14 | 0.00 | 100 | 16.1 | 0 | 8.05 | 0 | 29.81 | 0.00 | 106.00 |
| 107.00 | 8.82 | 0.00 | 100 | 14.96 | 0 | 7.48 | 0 | 27.70 | 0.00 | 107.00 |
| 108.00 | 8.62 | 0.00 | 100 | 17.44 | 0 | 8.72 | 0 | 32.30 | 0.00 | 108.00 |
| 109.00 | 8.82 | 0.13 | 100 | 17.44 | 0.13 | 8.72 | 0.065 | 32.30 | 0.24 | 109.00 |
| 110.00 | 10.44 | 0.00 | 100 | 19.26 | 0.13 | 9.63 | 0.065 | 35.67 | 0.24 | 110.00 |
| TOTAL GROSS VOLUMES THIS PAGE | | | | | | | | | 440.01 | 0.77 |

FILE NAME VILLAGE WIDE BIKE PATH - STAGE 2
 FAU RTE. 1459 (26TH STREET), FAU 2759
 (DESPLAINES AVENUE), VILLAGE COMMONS,
 HAINSWORTH AVENUE, 25TH STREET AND VETERANS
 PARK FROM FORESTVIEW AVENUE TO VETERAN DRIVE

USER NAME =
 PLOT SCALE = 1"=10'
 PLOT DATE =

DESIGNED -- THK
 DRAWN -- JFP-JEP
 CHECKED -- THK
 DATE -- 1-29-10

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

CROSS SECTIONS
 SCALE: SHEET NO. OF SHEETS STA. TO STA.

Frank Novotny & Associates, Inc.
 835 Midway Drive • Willowbrook, IL • 60527 • Telephone: (630) 897-8640 • Fax: (630) 897-0132
 ILLINOIS PROFESSIONAL DESIGN FIRM NO. 154-000928

F.A. SECTION COUNTY TOTAL SHEET NO.
 RTE. 06-00080-01-BT COOK 37 21
 VAR CONTRACT NO. 63461
 ILLINOIS FED. AID PROJECT HPP-3463(006)