

SUMMARY OF QUANTITIES				CONSTRUCTION CODE				
				80% FED 20% CITY	80% FED 20% CITY	80% FED 20% CITY	80% FED 20% CITY	80% FED 20% CITY
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003 URBAN	ROADWAY 0005 URBAN	SAFETY 0021 URBAN	LANDSCAPING 0031 URBAN	STRUCTURES 0040 URBAN
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	281	281				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	98	98				
20200100	EARTH EXCAVATION	CU YD	4126	4126				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	3951	3951				
20800150	TRENCH BACKFILL	CU YD	365	365				
21301060	EXPLORATION TRENCH 60" DEPTH	FOOT	300	300				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	7465				7465	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	93				93	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	93				93	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	93				93	
* 25200110	SODDING, SALT TOLERANT	SQ YD	7465				7465	
* 25200200	SUPPLEMENTAL WATERING	UNIT	75				75	
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	155	155				
28000400	PERIMETER EROSION BARRIER	FOOT	4100	4100				
28000510	INLET FILTERS	EACH	26	26				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4936	4936				
40600300	AGGREGATE (PRIME COAT)	TON	19	19				
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	200		200			
40600895	CONSTRUCTING TEST STRIP	EACH	3	3				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	58		58			
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	4510	4510				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1453	1061	392			
42001300	PROTECTIVE COAT	SQ YD	1200	1200				
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	20200			20200		
42400400	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	SQ FT	447			447		
42400800	DETECTABLE WARNINGS	SQ FT	40			40		
44000100	PAVEMENT REMOVAL	SQ YD	5225	5225				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	3500		3500			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1098	1098				

SUMMARY OF QUANTITIES				CONSTRUCTION CODE				
				80% FED 20% CITY	80% FED 20% CITY	80% FED 20% CITY	80% FED 20% CITY	80% FED 20% CITY
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003 URBAN	ROADWAY 0005 URBAN	SAFETY 0021 URBAN	STRUCTURES 0040 URBAN	TRAINEES 0042 URBAN
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2922	2922				
44000600	SIDEWALK REMOVAL	SQ FT	5143			5143		
44201709	CLASS D PATCHES, TYPE III, 5 INCH	SQ YD	166		166			
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	535		535			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	6850	6850				
50200100	STRUCTURE EXCAVATION	CU YD	104				104	
50300225	CONCRETE STRUCTURES	CU YD	26.7				26.7	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2450				2450	
50901760	PIPE HANDRAIL	FOOT	75				75	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1				
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	141	141				
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	477	477				
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	460	460				
55100500	STORM SEWER REMOVAL 12"	FOOT	111	111				
55100700	STORM SEWER REMOVAL 15"	FOOT	251	251				
55100900	STORM SEWER REMOVAL 18"	FOOT	317	317				
* 56400100	FIRE HYDRANTS TO BE MOVED	EACH	4	4				
* 56400400	FIRE HYDRANTS TO BE RELOCATED	EACH	1	1				
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	35	35				
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	8	8				
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1				
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	2	2				
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	5	5				
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4				
60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2	2				
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	4	4				
60500040	REMOVING MANHOLES	EACH	1	1				
60500050	REMOVING CATCH BASINS	EACH	3	3				
60500060	REMOVING INLETS	EACH	16	16				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1746	1746				

* SPECIALTY ITEMS

FILE NAME =	USER NAME = cesario	DESIGNED - BD	REVISED -
FA\396-064 Pingree Road\CADD\Sheets\Ildo	Format\DI63519-aht-50Q.Ldgn	DRAWN - DC	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED - BD	REVISED -
	PLOT DATE = 9/14/2011	DATE - 08-29-2011	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PINGREE ROAD RECONSTRUCTION
SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 3 OF 92 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
126	95-00090-01-FP	MCHEMRY	92	3
CONTRACT NO. 63519				
[ILLINOIS] FED. AID PROJECT				