

SUMMARY OF QUANTITIES				CONSTRUCTION CODE				
				80% FED 20% CITY	80% FED 20% CITY	80% FED 20% CITY	80% FED 20% CITY	80% FED 20% CITY
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003 URBAN	ROADWAY 0005 URBAN	SAFETY 0021 URBAN	STRUCTURES 0040 URBAN	TRAINEES 0042 URBAN
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2344	2344				
60618800	CONCRETE MEDIAN, TYPE SB	SQ FT	2303	2303				
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	7	7				
67100100	MOBILIZATION	L SUM	1	1				
70102620	TRAFFIC CONTROL & PROTECTION, STANDARD 701501	L SUM	1			1		
70102635	TRAFFIC CONTROL & PROTECTION, STANDARD 701701	L SUM	1			1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6			6		
72000100	SIGN PANEL - TYPE 1	SQ FT	30			30		
72000200	SIGN PANEL - TYPE 2	SQ FT	22			22		
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	433	433				
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6705	6705				
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2302	2302				
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1555	1555				
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	163	163				
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	576			576		
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	113			113		
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	25			25		
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	121			121		
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	315			315		
81400100	HANDHOLE	EACH	5			5		
81400200	HEAVY-DUTY HANDHOLE	EACH	2			2		
81400300	DOUBLE HANDHOLE	EACH	2			2		
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	677			677		
85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1			1		
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14, 2C	FOOT	411			411		
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14, 3C	FOOT	1300			1300		
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14, 5C	FOOT	2388			2388		
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14, 7C	FOOT	1267			1267		
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14, 1 PAIR	FOOT	1805			1805		

*** SPECIALTY ITEMS**

FILE NAME = F:\396-064 Pingree Road\CADD\Sheets\Ideo	USER NAME = cesario	DESIGNED - BD	REVISED -
Format\DIG3519-sht-S00.1.dgn		DRAWN - DC	REVISED -
PLOT SCALE = 50.0000' / IN.		CHECKED - BD	REVISED -
PLOT DATE = 9/14/2011		DATE - 08-29-2011	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**PINGREE ROAD RECONSTRUCTION
SUMMARY OF QUANTITIES**

SCALE: N.T.S. SHEET NO. 4 OF 92 SHEETS STA. TO STA.

SUMMARY OF QUANTITIES				CONSTRUCTION CODE				
				80% FED 20% CITY	80% FED 20% CITY	80% FED 20% CITY	80% FED 20% CITY	80% FED 20% CITY
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003 URBAN	ROADWAY 0005 URBAN	SAFETY 0021 URBAN	STRUCTURES 0040 URBAN	TRAINEES 0042 URBAN
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6, 2 C	FOOT	48			48		
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 14 FT.	EACH	1			1		
87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 15 FT.	EACH	1			1		
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 16 FT.	EACH	2			2		
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1			1		
87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1			1		
87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1			1		
87700310	STEEL MAST ARM ASSEMBLY AND POLE, 54 FT.	EACH	1			1		
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16			16		
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4			4		
87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	60			60		
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	7			7		
88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST-ARM MOUNTED	EACH	2			2		
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	2			2		
88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1			1		
88030230	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-4 SECTION, BRACKET MOUNTED	EACH	1			1		
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1			1		
88030250	SIGNAL HEAD, LED, 2-FACE, 1-4 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1			1		
88102710	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	2			2		
88102740	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED	EACH	1			1		
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	11			11		
88500100	INDUCTIVE LOOP DETECTOR	EACH	9			9		
88600700	PREFORMED DETECTOR LOOP	FOOT	837			837		
88700200	LIGHT DETECTOR	EACH	3			3		
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1			1		
88800100	PEDESTRIAN PUSH-BUTTON	EACH	4			4		

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
126	95-00090-01-FP	MCHENRY	92	4
CONTRACT NO. 63519				
ILLINOIS FED. AID PROJECT				