



**SCHEDULE OF QUANTITIES**

ITEM	UNIT	TOTAL
CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	2825
CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	450
HANDHOLE	EACH	3
TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2800
TRANSCEIVER - FIBER OPTIC	EACH	6
ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	5580
FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	5730



FILE NAME = 28_D23301-sh-t-ta03.dgn	USER NAME = USER:8291	DESIGNED - LC	REVISED -
PLOT SCALE = 1:100	CHECKED - CF	DRAWN - LC	REVISED -
PLOT DATE = 8/29/2011	DATE - 08/16/11		REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>INTERCONNECT SCHEMATIC</b>			
<b>SHERIDAN ROAD - CHICAGO AVENUE TO CENTRAL STREET</b>			
SCALE: N.T.S.	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.U. RTE. 2853	SECTION 10-00258-00-TL	COUNTY COOK	TOTAL SHEETS 38	SHEET NO. 28
CONTRACT NO. 63630				
ILLINOIS FED. AID PROJECT				