

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				75th STREET	
				ROADWAY 0003	TRAFFIC SIGNALS 0021
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	618	618	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	344	344	
20101000	TEMPORARY FENCE	FOOT	500	500	
20200100	EARTH EXCAVATION	CU YD	33,984	33,984	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	12,401	12,401	
20800150	TRENCH BACKFILL	CU YD	12,101	12,101	
* 21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	54,264	54,264	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	757	757	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	757	757	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	757	757	
* 25100630	EROSION CONTROL BLANKET	SQ YD	63,084	63,084	
* 25200100	SODDING	SQ YD	41,784	41,784	
* 25200110	SODDING, SALT TOLERANT	SQ YD	20,687	20,687	
* 25200200	SUPPLEMENTAL WATERING	UNIT	610	610	
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,303	1,303	
28000305	TEMPORARY DITCH CHECKS	FOOT	2,028	2,028	
28000400	PERIMETER EROSION BARRIER	FOOT	5,545	5,545	
28000500	INLET AND PIPE PROTECTION	EACH	92	92	
28000510	INLET FILTERS	EACH	225	225	
28100107	STONE RIPRAP, CLASS A4	SQ YD	43	43	
28200200	FILTER FABRIC	SQ YD	43	43	
31101180	SUBBASE GRANULAR MATERIAL, TYPE B 2"	SQ YD	10,714	10,714	
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	6,654	6,654	
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	14,205	14,205	
35400400	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	SQ YD	721	721	
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	158	158	
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	4,104	4,104	
35501320	HOT-MIX ASPHALT BASE COURSE, 9"	SQ YD	25,803	25,803	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	45	45	
40600300	AGGREGATE (PRIME COAT)	TON	213	213	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	11	11	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	

\* SPECIALTY ITEMS

FILE NAME = F:\451-030 75th st duppage dot\engineering\dr\avirga\451-030-ant-300.dgn



USER NAME = gellwanger	DESIGNED - GJE	REVISED - 3 11-16-11
PLOT SCALE = 20.0000' / IN.	DRAWN - DC	REVISED -
PLOT DATE = 9/8/2011	CHECKED - JP	REVISED -
	DATE - 9/08/11	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
75TH STREET

SCALE: NONE SHEET NO. 3 OF 198 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0369	07-00232-04-WR		198	3
CONTRACT NO. 63632			ILLINOIS FED. AID PROJECT	