

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				75th STREET	
				ROADWAY 0003	TRAFFIC SIGNALS 0021
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	202	202	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	239	239	
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	13,667	13,667	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1,223	1,223	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	10,630	10,630	
42001300	PROTECTIVE COAT	SQ YD	29,560	29,560	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	7,511	7,511	
42400800	DETECTABLE WARNINGS	SQ FT	2,066	2,066	
44000100	PAVEMENT REMOVAL	SQ YD	30,264	30,264	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	43,895	43,895	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	26,734	26,734	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	4,739	4,739	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	26,745	26,745	
44000600	SIDEWALK REMOVAL	SQ FT	47,090	47,090	
44003100	MEDIAN REMOVAL	SQ FT	9,706	9,706	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	215	215	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	208	208	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	468	468	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	56,799	56,799	
50105220	PIPE CULVERT REMOVAL	FOOT	855	855	
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	286	286	
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	218	218	
542A0226	PIPE CULVERTS, CLASS A, TYPE 1 21"	FOOT	92	92	
542A1060	PIPE CULVERTS, CLASS A, TYPE 2 15"	FOOT	63	63	
542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	121	121	
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	62	62	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	19	19	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	16	16	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	4	4	
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	5	5	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	4	4	
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1	

\* SPECIALTY ITEMS

FILE NAME = F:\451-930 75th St Dup.dgn DOT\ENGINEERING\DRAWINGS\451-930-shy-S00.dgn



USER NAME = elarson	DESIGNED - GJE	REVISED -
PLOT SCALE = 20.0000' / IN.	DRAWN - DC	REVISED -
PLOT DATE = 9/13/2011	CHECKED - JP	REVISED -
	DATE - 9/08/11	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
75TH STREET**

SCALE: NONE      SHEET NO. 4 OF 198 SHEETS      STA.      TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0369	07-00232-04-WR	DuPAGE	198	4
CONTRACT NO. 63632			ILLINOIS FED. AID PROJECT	