

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				75th STREET	
				ROADWAY 0003	TRAFFIC SIGNALS 0021
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	4	4	
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	1	1	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	6,362	6,362	
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	453	453	
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	128	128	
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	62	62	
550A0180	STORM SEWERS, CLASS A, TYPE 1 42"	FOOT	14	14	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	2,314	2,314	
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	107	107	
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	43	43	
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	580	580	
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	1,858	1,858	
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	893	893	
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	625	625	
550A0680	STORM SEWERS, CLASS A, TYPE 3 18"	FOOT	69	69	
550A0750	STORM SEWERS, CLASS A, TYPE 3 36"	FOOT	291	291	
550A4500	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36"	FOOT	134	134	
550A4700	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 42"	FOOT	208	208	
550A5300	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 36"	FOOT	47	47	
550A5500	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 42"	FOOT	814	814	
550A5510	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 48"	FOOT	65	65	
55100100	STORM SEWER REMOVAL 4"	FOOT	31	31	
55100400	STORM SEWER REMOVAL 10"	FOOT	102	102	
55100500	STORM SEWER REMOVAL 12"	FOOT	1,498	1,498	
55100700	STORM SEWER REMOVAL 15"	FOOT	1,551	1,551	
55100900	STORM SEWER REMOVAL 18"	FOOT	610	610	
55101200	STORM SEWER REMOVAL 24"	FOOT	1,692	1,692	
55101600	STORM SEWER REMOVAL 36"	FOOT	171	171	
* 56400100	FIRE HYDRANTS TO BE MOVED	EACH	8	8	
* 56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	14	14	

\* SPECIALTY ITEMS

FILE NAME = f:\151-038 75th st dupage dot\engineering\drwings\151-038-111-500.dgn



USER NAME = gellwanger  
 PLOT SCALE = 20.0000' / IN.  
 PLOT DATE = 9/8/2011

DESIGNED - GJE  
 DRAWN - DC  
 CHECKED - JP  
 DATE - 9/08/11

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
 75TH STREET

SCALE: NONE SHEET NO. 5 OF 198 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0369	07-00232-04-WR	DUPAGE	198	5
CONTRACT NO. 63632				
ILLINOIS FED. AID PROJECT				