

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONSTRUCTION CODE | |
|------------|---|-------|----------------|-------------------|-------------------------|
| | | | | 75th STREET | |
| | | | | ROADWAY 0003 | TRAFFIC SIGNALS 0021 |
| * 78008210 | POLYUREA PAVEMENT MARKING TYPE I - LINE 4" | FOOT | 64 | 64 | |
| * 78008230 | POLYUREA PAVEMENT MARKING TYPE I - LINE 6" | FOOT | 565 | 565 | |
| * 78008270 | POLYUREA PAVEMENT MARKING TYPE I - LINE 24" | FOOT | 37 | 37 | |
| * 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 195 | 195 | |
| * 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 2,240 | 2,240 | |
| * 80500020 | SERVICE INSTALLATION - POLE MOUNTED | EACH | 2 | | 2 |
| * 81000600 | CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL | FOOT | 7,533 | | 7,533 |
| * 81000700 | CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL | FOOT | 37 | | 37 |
| * 81000800 | CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL | FOOT | 299 | | 299 |
| * 81001000 | CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL | FOOT | 356 | | 356 |
| * 81018500 | CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL | FOOT | 2,299 | | 2,299 |
| * 81018900 | CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL | FOOT | 1,163 | | 1,163 |
| * 81400100 | HANDHOLE | EACH | 30 | | 30 |
| * 81400300 | DOUBLE HANDHOLE | EACH | 4 | | 4 |
| * 81700110 | ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 10 | FOOT | 4,718 | | 4,718 |
| * 81900200 | TRENCH AND BACKFILL FOR ELECTRICAL WORK | FOOT | 8,225 | | 8,225 |
| * 82102400 | LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT | EACH | 8 | | 8 |
| * 85700200 | FULL-ACTUATED CONTROLLER AND TYPE IV CABINET | EACH | 1 | | 1 |
| * 85700300 | FULL-ACTUATED CONTROLLER AND TYPE V CABINET | EACH | 1 | | 1 |
| * 86000100 | MASTER CONTROLLER | EACH | 1 | | 1 |
| * 86200120 | UNINTERRUPTIBLE POWER SUPPLY | EACH | 2 | | 2 |
| * 86400100 | TRANSCEIVER - FIBER OPTIC | EACH | 3 | | 3 |
| * 87100020 | FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F | FOOT | 16,166 | | 16,166 |
| * 87300925 | ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C | FOOT | 15,974 | | 15,974 |
| * 87301215 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C | FOOT | 3,463 | | 3,463 |
| * 87301225 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C | FOOT | 4,635 | | 4,635 |
| * 87301245 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C | FOOT | 8,742 | | 8,742 |
| * 87301255 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C | FOOT | 2,998 | | 2,998 |
| * 87301305 | ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR | FOOT | 17,033 | | 17,033 |
| * 87301805 | ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C | FOOT | 56 | | 56 |
| * 87501000 | TRAFFIC SIGNAL POST, 14 FT. | EACH | 2 | | 2 |
| * 87501200 | TRAFFIC SIGNAL POST, 16 FT. | EACH | 2 | | 2 |
| * 87700160 | STEEL MAST ARM ASSEMBLY AND POLE, 24 FT. | EACH | 2 | | 2 |

* SPECIALTY ITEMS

FILE NAME = F:\451-938 75th St Dup.dwg DOT ENGINEERING\DRAWINGS\451-938-ht-500.dwg



| | | |
|--------------------------------|----------------|-----------|
| USER NAME = olarson | DESIGNED - GJE | REVISED - |
| PLOT SCALE = 20.0000' / 1" IN. | DRAWN - DC | REVISED - |
| PLOT DATE = 9/13/2011 | CHECKED - JP | REVISED - |
| | DATE - 9/08/11 | REVISED - |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
75TH STREET**

SCALE: NONE SHEET NO. 8 OF 198 SHEETS STA. TO STA.

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------------|----------------|--------|--------------------|-----------|
| 0369 | 07-00232-04-WR | DuPAGE | 198 | 8 |
| | | | CONTRACT NO. 63632 | |
| ILLINOIS FED. AID PROJECT | | | | |