



LOCATION STA. TO STA.	LANDSCAPING			FERTILIZER (SODDING RATE 60 LBS/ACRE)			
	TOPSOIL FURNISH AND PLACE 6" (SQ. YD)	SODDING, SALT TOLERANT (SQ. YD)	SODDING (SQ YD)	SUPPLEMENTAL WATERING (UNIT)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHOROUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)
STA. 527+00 TO STA. 542+00	---	3645	8141	118	146	146	146
STA. 542+00 TO STA. 557+00	---	3240	9227	125	155	155	155

NOTE: SODDING, SALT-TOLERANT IS TO BE USED IN THE MEDIANS AND WITHIN 10 FEET FROM THE BACK OF CURB. SODDING WILL BE USED IN ALL OTHER LOCATIONS.

FILE NAME = F:\451-938 75th St. Dupage DOT\ENGINEERING\DRAWINGS\451-938-ahh-pmk-1\ndesp2.dgn



USER NAME = alerson	DESIGNED - GJE	REVISED -
PLOT SCALE = 50.0000' / IN.	DRAWN - DC	REVISED -
PLOT DATE = 9/13/2011	CHECKED - JP	REVISED -
	DATE - 9/08/11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PAVMENT MARKING AND LANDSCAPING PLAN
75TH STREET

SCALE: 1"=50' SHEET NO. 97 OF 198 SHEETS STA. 527+00 TO STA. 557+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0369	07-00232-04-WR	DuPAGE	198	97
				CONTRACT NO. 63632
ILLINOIS FED. AID PROJECT				