



SCHEDULE OF QUANTITIES

ITEM	UNIT	QTY.
CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	5,518
CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	1,753
HANDHOLE	EACH	10
TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	5,518
FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	16,166
ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	15,974
DRILL EXISTING HANDHOLE	EACH	4
DETECTOR LOOP, TYPE I	FOOT	255

FILE NAME = F:\451-030 75th st dupage dot\engineering\drawings\451-030-011-10-interconnect.schematic2.dgn



USER NAME = gellwenger
 PLOT SCALE = 50,0000 ' / IN.
 PLOT DATE = 9/7/2011

DESIGNED - GJE
 DRAWN - DC
 CHECKED - JP
 DATE - 9/08/11

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**INTERCONNECT SCHEMATIC
 LEMONT ROAD
 FROM CHESTNUT CT TO DUNHAM RD**

SCALE: NONE SHEET NO. 133 OF 198 SHEETS STA. TO STA.

F.A.P. RTE. 0369	SECTION 07-00232-04-WR	COUNTY DuPAGE	TOTAL SHEETS 198	SHEET NO. 133
CONTRACT NO. 63632				
ILLINOIS FED. AID PROJECT				