

# SUMMARY OF QUANTITIES

SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
					80% FEDERAL 20% STATE	
					LANDSCAPING 0031 URBAN	TRAINEES 042 URBAN
*	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1,171		
*	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	882	882	
	20101000	TEMPORARY FENCE	FOOT	2,497	2497	
	20101100	TREE TRUNK PROTECTION	EACH	11	11	
	20101700	SUPPLEMENTAL WATERING	UNIT	90	90	
*	20200100	EARTH EXCAVATION	CU YD	5,525	5525	
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	6,850	6850	
	20800150	TRENCH BACKFILL	CU YD	11	11	
*	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	600	600	
	21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	3,065	3065	
	25000115	SEEDING, CLASS 1B	ACRE	1.75	1.75	
	25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25	
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	180	180	
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	180	180	
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	180	180	
	25100115	MULCH, METHOD 2	ACRE	39.75	39.75	
	25100630	EROSION CONTROL BLANKET	SQ YD	30,319	30319	
	25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	2,080	2080	
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	400	400	
	28000305	TEMPORARY DITCH CHECKS	FOOT	1,067	1067	
	28000315	AGGREGATE DITCH CHECKS	TON	33	33	
	28000400	PERIMETER EROSION BARRIER	FOOT	4,600	4600	
	28000500	INLET AND PIPE PROTECTION	EACH	14	14	
	28000510	INLET FILTERS	EACH	17	17	
	28200200	FILTER FABRIC	SQ YD	1,312	1312	
*	35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	7,069	7069	
*	35102400	AGGREGATE BASE COURSE, TYPE B 12"	SQ YD	1,243	1243	
*	40200900	AGGREGATE SURFACE COURSE, TYPE B	CU YD	166	166	
*	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10	10	
*	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	568	568	
*	42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	768	768	
*	44000100	PAVEMENT REMOVAL	SQ YD	13	13	
*	44004250	PAVED SHOULDER REMOVAL	SQ YD	50	50	
*	48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	26	26	
*	48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	9	9	

FILE NAME = M:\Projects\2011\10131\SeserveR22A\esdd\Civil\Drawn\Shd\S00\_110131\_01.dgn



USER NAME = #USER#	DESIGNED - PJF	REVISED -
PLOT SCALE =	DRAWN - NDP	REVISED -
PLOT DATE = 8/30/2011	CHECKED - PDK	REVISED -
	DATE - 8/29/11	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**MCLEAN BLVD ENVIRONMENTAL ADAPTIVE MANAGEMENT PLANS  
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 3 OF 54 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
361	06-00214-11-LS	KANE	54	3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 63638	