SUMMARY OF QUANTITIES				CONSTRUCTION CODE		
				80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL
IDOT ITEM NO.	PAY ITEM	UNIT	TOTAL QTY.	0004 ROADWAY URBAN	0021 SAFETY URBAN	0031 LANDSCAPING URBAN
20200100	EARTH EXCAVATION	CU YD	165	165		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	310	310		
20400800	FURNISHED EXCAVATION	CU YD	10	10		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	756			756
25000100	SEEDING, CLASS 1	ACRE	0.25			0.25
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23			23
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23			23
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23			23
28000400	PERIMETER EROSION BARRIER	FOOT	2775	2775		
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	2696	2696		
42001300	PROTECTIVE COAT	SQ YD	53	53		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	16119.0		16119.0	
42400400	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	SQ FT	4033.0		4033.0	
42400800	DETECTABLE WARNINGS	SQ FT	180.0		180.0	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	645	645		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	246	246		
44000600	SIDEWALK REMOVAL	SQ FT	3446.0	3446.0		
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	324	324		
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	7	7		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	246.0	246.0		
67100100	MOBILIZATION	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		1	
72000200	SIGN PANEL- TYPE 2	SQ FT	120		120	
72900200	METAL POST- TYPE B	FOOT	150		150	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	907	907		
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	192	192		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	24	24		

* SPECIALTY ITEMS

HMA MIXTURE REQUIREMENTS CHART MIXTURE TYPE	AIR VOIDS @ Ndes	THICKNESS
PAVEMENT PATCHING CLASS D PATCHES, TYPE II, 7 INCH HOT-MIX ASPHALT BASE COURSE (HMA BINDER, IL-19mm)	4% @ 70 GYR.	7" IN TWO LIFTS

FOR NON-POLYMERIZED HMA THE "AC TYPE" SHALL BE "PG-64-22" UNLESS MODIFIED BY DISTRICT ONE SPECIAL PROVISIONS.

FOR "PERCENT OF RAP" SEE DISTRICT ONE SPECIAL PROVISIONS.