

CODE NUMBER	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL	FEDERAL 80% / STATE 20%			CITY OF STERLING 100%			CITY OF ROCK FALLS 100%	
				SAFETY 0021	Roadway 0004	Bridge 0011	LANDSCAPING 0031	SAFETY 0021	Roadway 0004	SAFETY 0021	Roadway 0004
60500040	REMOVING MANHOLES	EACH	1		1						
60500060	REMOVING INLETS	EACH	5		5						
60500105	FILLING MANHOLES	EACH	1		1						
60600605	CONCRETE CURB, TYPE B	FOOT	44		44						
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	378		378						
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	30		30						
60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	337		337						
60607400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24	FOOT	700		700						
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	629		629						
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	138		138						
63200400	CABLE ROAD GUARD REMOVAL	FOOT	43		43						
63500310	REMOVE AND REINSTALL DELINEATORS	EACH	43		43						
66700305	* PERMANENT SURVEY MARKERS, TYPE II	EACH	1		1						
66900200	* NON-SPECIAL WASTE DISPOSAL	CU YD	555		555						
66900205	* SPECIAL WASTE DISPOSAL	CU YD	13		13						
66900210	* HAZARDOUS WASTE DISPOSAL	CU YD	2		2						
66900400	* SPECIAL WASTE GROUNDWATER DISPOSAL	GALLON	300		300						
66900450	* SPECIAL WASTE PLANS AND REPORT	L SUM	1		1						
66900530	* SOIL DISPOSAL ANALYSIS	EACH	5		5						
66900535	* PRIORITY POLLUTANTS GROUNDWATER ANALYSIS	EACH	1		1						
66900665	* TCL SOIL ANALYSIS	EACH	2		2						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12		12						
67100100	MOBILIZATION	L SUM	1		1						
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1		1						
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		1						
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1						
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		1						
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30		30						
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4		4						
70300100	* SHORT TERM PAVEMENT MARKING	FOOT	725		725						

\* SPECIALTY ITEM

FILE NAME =	USER NAME = hersonke	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL 40 SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca:\pvc\work\proj\dot\hersonke\dms80258\026	4880-shr-5004.dgn	DRAWN - DMW	REVISED -		SCALE: N/A	SHEET NO. 4 OF 7 SHEETS	STA.	TO STA.	646	1B-2	WHITESIDE	257	6
	PLOT SCALE = N/A	CHECKED -	REVISED -							CONTRACT NO. 64B80			
	PLOT DATE = Tue Sep 27 13:33:04 2011	DATE - 2-22-2010	REVISED -							ILLINOIS FED. AID PROJECT			