

CODE NUMBER	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL	FEDERAL 80% / STATE 20%			CITY OF STERLING 100%		CITY OF ROCK FALLS 100%	
				SAFETY 0021	Roadway 0004	Bridge 0011	LANDSCAPING 0031	SAFETY 0021	Roadway 0004	SAFETY 0021
81012600	* CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	331	331						
81028320	* UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	2	2						
81100600	* CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	10	10						
81101000	* CONDUIT ATTACHED TO STRUCTURE, 4" DIA., GALVANIZED STEEL	FOOT	2,054	2,054						
81200230	* CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	2,190	2,190						
81400100	* HANDHOLE	EACH	2	2						
81400730	* HANDHOLE, COMPOSITE CONCRETE	EACH	3	3						
81702130	* ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	3,193	3,193						
81702140	* ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	6,386	6,386						
81702150	* ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	9,406	9,406						
81800200	* AERIAL CABLE, 2-1/C NO. 4 WITH MESSENGER WIRE	FOOT	1,008	1,008						
81900200	* TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	805	805						
82500390	* LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 100AMP (DUAL)	EACH	1	1						
83600200	* LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	25	25						
84200600	* REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	6	6						
85000200	* MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	2						
87301245	* ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	193	193						
87301255	* ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	125	125						
87301305	* ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1PAIR	FOOT	182	182						
87301515	* ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR	FOOT	65	65						
87301900	* ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	194	194						
87800100	* CONCRETE FOUNDATION, TYPE A	FOOT	3	3						
87900200	* DRILL EXISTING HANDHOLE	EACH	3	3						
88600100	* DETECTOR LOOP, TYPE I	FOOT	131	131						
88040150	* SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1	1						
88040160	* SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1	1						
88102845	* PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	6	6						
88200100	* TRAFFIC SIGNAL BACKPLATE	EACH	1	1						
89501150	* RELOCATE EXISTING TRAFFIC SIGNAL POST	EACH	1	1						
89502210	* MODIFY EXISTING CONTROLLER CABINET	EACH	1	1						

* SPECIALTY ITEM

FILE NAME =	USER NAME = hansonke	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 40 SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\hansonke\dms88258\0284880-ht-5006.dgn		DRAWN - DMW	REVISED -		SCALE: N/A	SHEET NO. 6 OF 7 SHEETS	STA.	TO STA.	646	IB-2	WHITESIDE	257	8
		PLOT SCALE = N/A	REVISED -						CONTRACT NO. 64B80				
		PLOT DATE = Tue Sep 27 13:38:05 2011	REVISED -						ILLINOIS FED. AID PROJECT				