

THERMOPLASTIC PAVEMENT MARKING SCHEDULE

LOCATION				REMARKS	78000100 THERMOPLASTIC PAVEMENT MARKING LETTERS AND SYMBOLS (SQ FT)	78000200 THERMOPLASTIC PAVEMENT MARKING LINE 4" (FOOT)	78000400 THERMOPLASTIC PAVEMENT MARKING LINE 6" (FOOT)	78000500 THERMOPLASTIC PAVEMENT MARKING LINE 8" (FOOT)	78000600 THERMOPLASTIC PAVEMENT MARKING LINE 12" (FOOT)	78000650 THERMOPLASTIC PAVEMENT MARKING LINE 24" (FOOT)
716+01.6	RT			LEFT ARROW - 3 EACH	46.8					
719+29.6	LT			LEFT ARROW - 3 EACH	46.8					
721+15.6	LT			LEFT ARROW - 3 EACH	46.8					
715+54.8	RT	719+64.75	RT	SKIP DASH 4" (10' / 30')		102.5				
720+70.8	RT	722+75.79	RT	SKIP DASH 4" (10' / 30')		51.3				
715+61.3	LT	719+71.29	LT	SKIP DASH 4" (10' / 30')		102.5				
720+73.0	LT	722+75.79	LT	SKIP DASH 4" (10' / 30')		50.7				
740+22.9	LT	741+29.91	LT	SKIP DASH 4" (10' / 30')		45.1				
741+29.9	LT	743+73.36	LT	SKIP DASH 4" (10' / 30')		60.9				
715+54.7	RT	716+73.15	RT	2 LINES		236.9				
716+73.2	RT	716+97.70	LT	1 LINE		24.8				
716+97.7	LT	717+78.46	LT	2 LINES		162.2				
717+78.5	LT	718+37.00	LT	2 LINES		117.1				
718+37.0	LT	718+65.21	LT	1 LINE		28.2				
718+65.2	LT	719+79.49	LT	2 LINES		228.6				
716+73.2	RT	716+97.67	RT	1 LINE		24.5				
716+97.7	RT	717+58.39	RT	2 LINES		121.4				
717+58.4	RT	718+37.66	LT	2 LINES		159.5				
718+37.7	LT	718+65.21	LT	1 LINE		27.7				
742+18.0	LT	742+84.00	LT	LOCUST ST PARKING		36.0				
715+42.8				CROSSWALK - IL 40 & 3RD ST			77.6			
715+48.8				CROSSWALK - IL 40 & 3RD ST			71.0			
719+90.5				CROSSWALK - IL 40 & 2ND ST			69.8			
719+96.6				CROSSWALK - IL 40 & 2ND ST			81.6			
720+25.2	LT			CROSSWALK - IL 40 & 2ND ST			47.8			
720+26.8	LT			CROSSWALK - IL 40 & 2ND ST			52.4			
720+48.8				CROSSWALK - IL 40 & 2ND ST			76.1			
720+58.8				CROSSWALK - IL 40 & 2ND ST			69.9			
720+20.6	RT			CROSSWALK - IL 40 & 2ND ST			56.0			
720+14.9	RT			CROSSWALK - IL 40 & 2ND ST			56.5			
717+58.4	RT	717+78.06	RT	SKIP DASH 8" (2' / 4')			6.6			
716+46.1	LT	717+78.46	LT	SKIP DASH 8" (2' / 4')			44.1			
721+64.1	LT	722+49.77	LT	SKIP DASH 8" (2' / 4')			28.6			
718+78.1	RT	719+81.80	RT	SOLID 8"			103.7			
715+54.8	LT	716+46.12	RT	SOLID 8"			93.5			
720+64.8	LT	721+64.05	LT	SOLID 8"			99.2			
740+04.7	LT	740+05.07	LT	SOLID 8"			13.6			
740+05.1	LT	741+33.08	LT	SOLID 8"			202.1			
741+33.1	LT	741+58.30	LT	SOLID 8"			25.2			
742+18.2	LT	743+78.25	LT	SOLID 8"			175.1			
740+43.9	LT	740+44.69	LT	SOLID 8"			17.1			
740+44.7	LT	741+45.22	LT	SOLID 8"			158.6			
741+45.2	LT	743+68.48	LT	SOLID 8"			223.3			
716+81.2		718+53.12		DIAGONAL MEDIAN				66.9		
740+43.9	LT	741+45.22	LT	DIAGONAL PAVEMENT NARROWING				185.6		
719+78.8	LT			STOP BAR - NB IL 40						11.0
719+82.7	RT			STOP BAR - NB IL 40						23.5
715+53.9	LT			STOP BAR - SB IL 40						22.0
715+55.8	LT			STOP BAR - SB IL 40						11.0
720+63.8	LT			STOP BAR - SB IL 40						24.0
720+65.9	LT			STOP BAR - SB IL 40						11.0
720+11.4	LT			STOP BAR - 2ND ST						15.1
720+29.4	RT			STOP BAR - 2ND ST						27.7
TOTAL					140.4	1,579.8	658.7	1,190.8	252.5	145.3
ROUNDED					141.0	1,580.0	659.0	1,191.0	253.0	146.0

78200520 BARRIER WALL MARKERS, TYPE B					
LOCATION		FOOT		REMARKS	
724+17.82	RT	735+07.88	RT	16	PER STANDARD 635006 BARRIER MARKERS ARE SPACED 80' FOR THE FIRST 400' AND THEN EVERY 400'.
724+17.82	LT	735+07.88	LT	16	
TOTAL			32		

FILE NAME = D264B88-sh-t-schedule7.dgn
 USER NAME = dwozniorak
 PLOT SCALE = N/A
 PLOT DATE = 7/14/2011

DESIGNED -
 DRAWN - DMW
 CHECKED -
 DATE - 2-22-2010
 REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

IL 40
 SCHEDULE OF QUANTITIES
 SCALE: N/A SHEET NO. 7 OF 9 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
646	1B-2	WHITESIDE	257	22
CONTRACT NO. 64B80			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	