

ITEM 70301000 WORK ZONE PAVEMENT MARKING REMOVAL			
LOCATION STATION TO STATION	OFFSET	AREA (SQ FT)	COMMENT
US 52/IL 26			
386+37.27 TO 397+76.87	RT	381	STAGE 1
387+77.74 TO 396+82.84	LT	302	STAGE 1
386+97.00 TO 398+09.27	LT	372	STAGE 2
387+90.33 TO 396+53.75	RT	288	STAGE 2
386+27.27	RT	12	STAGE 2
398+36.87	LT	12	STAGE 2
TOTAL		1367	

ITEM 70400100 TEMPORARY CONCRETE BARRIER		
LOCATION STATION TO STATION	LENGTH (FOOT)	COMMENT
US 52/IL 26		
388+00.00 TO 394+75.00	675	STAGE 1
TOTAL	675	

ITEM 70400200 RELOCATE TEMPORARY CONCRETE BARRIER		
LOCATION STATION TO STATION	LENGTH (FOOT)	COMMENT
US 52/IL 26		
388+12.50 TO 394+75.00	662.5	STAGE 2
TOTAL	662.5	

ITEM 78001110 PAINT PAVEMENT MARKING - LINE 4"			
LOCATION STATION TO STATION	OFFSET	LENGTH (FOOT)	COMMENT
US 52/IL 26			
385+01.84 TO 398+19.27	LT	2636	SOLID WHITE
385+03.07 TO 398+19.27	RT	2634	SOLID WHITE
385+01.84 TO 398+19.27		660	YELLOW SKIP-DASH 30'-10'
TOTAL		5930	

ITEM 78100100 RAISED REFLECTIVE PAVEMENT MARKER		
LOCATION STATION TO STATION	LENGTH (FOOT)	COMMENT
US 52/IL 26		
385+01.84 TO 390+50.00	6	
393+39.70 TO 395+00.00	2	
TOTAL	8	

ITEM 78200410 GUARDRAIL MARKERS, TYPE A		
LOCATION STATION TO STATION	OFFSET	(EACH)
US 52/IL 26		
385+17.27 TO 389+85.42	LT	6
385+17.27 TO 389+85.42	RT	6
393+24.70 TO 394+92.85	LT	5
393+24.70 TO 394+92.85	RT	5
TOTAL		22

ITEM 78200520 BARRIER WALL MARKERS, TYPE B		
LOCATION STATION TO STATION	OFFSET	(EACH)
US 52/IL 26		
389+85.42 TO 393+24.70	LT	4
389+85.42 TO 393+24.70	RT	4
TOTAL		8

ITEM 78201000 TERMINAL MARKER - DIRECT APPLIED		
LOCATION STATION TO STATION	OFFSET	(EACH)
US 52/IL 26		
385+17.27	LT	1
385+17.27	RT	1
394+92.85	LT	1
394+92.85	RT	1
TOTAL		4

ITEM 78300100 PAVEMENT MARKING REMOVAL			
LOCATION STATION TO STATION	OFFSET	AREA (SQ FT)	COMMENT
US 52/IL 26			
385+01.84 TO 398+19.27	LT	440	SOLID WHITE
385+03.07 TO 398+19.27	RT	439	SOLID WHITE
385+01.84 TO 398+19.27		110	YELLOW SKIP-DASH 30'-10'
TOTAL		989	

ITEM Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3		
LOCATION STATION TO STATION	OFFSET	(EACH)
US 52/IL 26		
388+00.00	RT	1
394+75.00	RT	1
TOTAL		2

ITEM Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3		
LOCATION STATION TO STATION	OFFSET	(EACH)
US 52/IL 26		
388+12.50	LT	1
394+75.00	RT	1
TOTAL		2

ITEM Z0041700 PLUG EXISTING STORM SEWERS		
LOCATION STATION TO STATION	OFFSET	(EACH)
US 52/IL 26		
392+94.64	83.40 RT	1
394+65.10	16.80 RT	1
TOTAL		2

ITEM X4401198 HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	
LOCATION STATION TO STATION	AREA (SQ YD)
US 52/IL 26	
393+93.90 TO 395+00.00	471
TOTAL	471

ITEM A2C056G5 TREE, QUERCUS MACROCARPA (BURR OAK), CONTAINER GROWN, 5-GALLON	
LOCATION STATION TO STATION	(EACH)
US 52/IL 26	
	1
	1
	1
	1
	1
TOTAL	5

LOCATION AS DIRECTED BY DISTRICT LANDSCAPE ENGINEER