

SUMMARY OF QUANTITIES

CODE	ITEM	UNIT	TOTAL	CONSTRUCTION CODE			
				80% FEDERAL 20% STATE			
				ROADWAY 0004 RURAL	SN 052-0080 0011 RURAL	SN 052-2031 0011 RURAL	SN 052-0081 0011 RURAL
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	150	150			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	196	196			
20200100	EARTH EXCAVATION	CU YD	2,447	2,447			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	318	16		302	
20400800	FURNISHED EXCAVATION	CU YD	1,837	1,837			
* 25000210	SEEDING, CLASS 2A	ACRE	2.5	2.5			
* 25000310	SEEDING, CLASS 4	ACRE	0.75	0.75			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	286	286			
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	286	286			
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	286	286			
Δ 25000750	MOWING	ACRE	2.5	2.5			
* 25100115	MULCH, METHOD 2	ACRE	0.75	0.75			
* 25100630	EROSION CONTROL BLANKET	SQ YD	12,168	12,168			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1,905	1,905			
28000305	TEMPORARY DITCH CHECKS	FOOT	299	299			
28000400	PERIMETER EROSION BARRIER	FOOT	1,844	1,844			
28000500	INLET AND PIPE PROTECTION	EACH	3	3			
28100107	STONE RIPRAP, CLASS A4	SQ YD	123			123	
28100109	STONE RIPRAP, CLASS A5	SQ YD	2,384	105	1,085		1,194
28200200	FILTER FABRIC	SQ YD	2,507	105	1,085	123	1,194
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	1,114	1,114			
35100100	AGGREGATE BASE COURSE, TYPE A	TON	1,551	1,551			
35101400	AGGREGATE BASE COURSE, TYPE B	TON	278	278			
40600525	LEVELING BINDER (HAND METHOD), N50	TON	6	6			
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1,038	1,038			
40600990	TEMPORARY RAMP	SQ YD	196	196			
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,011	1,011			
40800050	INCIDENTIAL HOT-MIX ASPHALT SURFACING	TON	18	18			
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	112	112			

* SPECIALITY ITEM Δ NP 100% STATE

• 102BR-5, 102BR-6 & 102BR-7

FILE NAME =	USER NAME = grantpm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\grantpm\dms41810\021007-sht-schedule.dgn		DRAWN -	REVISED -		316		LEE	216	3				
PLOT SCALE = 75.0000' / 1in.		CHECKED -	REVISED -						CONTRACT NO. 64D57				
PLOT DATE = Tue Aug 23 06:28:41 2011		DATE -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		