

SUMMARY OF QUANTITIES

CODE	ITEM	UNIT	TOTAL	CONSTRUCTION CODE			
				80% FEDERAL 20% STATE			
				ROADWAY 0004 RURAL	SN 052-0080 0011 RURAL	SN 052-2031 0011 RURAL	SN 052-0081 0011 RURAL
542D0223	PIPE CULVERTS, CLASS D, TYPE 118"	FOOT	58	58			
542D0229	PIPE CULVERTS, CLASS D, TYPE 124"	FOOT	52	52			
54213447	END SECTIONS 12"	EACH	4	4			
54213453	END SECTIONS 18"	EACH	2	2			
54213459	END SECTIONS 24"	EACH	2	2			
54215408	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 8"	EACH	1	1			
54215410	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 10"	EACH	1	1			
54215412	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 12"	EACH	1	1			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	135		67		68
60100925	PIPE DRAINS 8"	FOOT	20	20			
60100935	PIPE DRAINS 10"	FOOT	20	20			
60100945	PIPE DRAINS 12"	FOOT	142	142			
60900515	CONCRETE THRUST BLOCKS	EACH	4	4			
61000115	TYPE E INLET BOX, STANDARD 610001	EACH	4	4			
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	20	20			
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	2	2			
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	700	700			
* 63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	100			100	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8	8			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	2	2			
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) FLARED	EACH	10	10			
63200310	GUARDRAIL REMOVAL	FOOT	2,514	2,514			
63500105	DELINEATORS	EACH	20	20			
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	18	18			
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	4	4			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8			
67100100	MOBILIZATION	L SUM	1	1			
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	3	3			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1			

* SPECIALITY ITEM