

EARTHWORK SCHEDULE

EARTHWORK SCHEDULE						
20200100			20400800			
LOCATION	EARTH EXCAVATION	EARTH EXC ADJ SHRINK 25% EARTH	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)	FURNISHED EXCAVATION	
	CU YD	CU YD	CU YD	CU YD	CU YD	
MAINLINE (IL 26)						
307 + 75 - 313 + 00	245.0	183.8	1,392.6	-1,208.9	1,208.9	
313 + 00 - 315 + 50	117.5	88.1	354.0	-265.9	265.9	
322 + 00 - 327 + 00	1,114.6	836.0	610.6	225.4		
327 + 00 - 329 + 50	228.8	171.6	235.0	-63.4	63.4	
415 + 25 - 418 + 00	152.8	114.6	33.1	81.5		
418 + 00 - 424 + 00	430.4	322.8	930.6	-607.8	607.8	
424 + 00 - 425 + 50	157.8	118.4	116.0	2.4		
TOTAL	2,446.9	1,835.2	3,671.9	-1,836.7	1,836.7	