

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(5CS,13C,108,109R)	KENDALL	931	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

SPEC. PROV. SPECIALTY ITEM	CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	FEDERAL = 80% STATE = 20% CITY=0%				FEDERAL = 80% STATE = 10% CITY = 10%						FEDERAL=80%	FEDERAL=80%	FEDERAL = 0% STATE = 0% CITY = 100%				
					ROADWAY	FOX RIVER BRIDGE REHABILITATION	IL 126 TRAFFIC SIGNALS	US 34 TRAFFIC SIGNALS	FOUNTAINVIEW DRIVE TRAFFIC SIGNALS	FOX STREET TRAFFIC SIGNALS	VAN EMMON STREET TRAFFIC SIGNALS	SOMONAUK STREET TRAFFIC SIGNALS	LANDMARK AVENUE TRAFFIC SIGNALS	COUNTRYSIDE PARKWAY TRAFFIC SIGNALS	CENTER PARKWAY TRAFFIC SIGNALS	SIDEWALK AND TRAIL REPL.	SIGNAL PRE-EMPTION (DISTRICT 1 CMAP)	ROADWAY (SOMONAUK STREET)	SAFETY AND LIGHTING	STREETSCAPE ENHANCEMENTS	UTILITIES
					0003	0014	0021		0021						0028	0021	0003	0021	0031	0043	
					01	01	01	02	03	04	05	06	07	08	09	01	10	01	01	01	01
* #	X8570225	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	8	1		1		1	1		1	1	1							
* #	X8570230	FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	2			1			1											
* #	86000100	MASTER CONTROLLER	EACH	2	2																
* #	86200300	UNINTERRUPTIBLE POWER SUPPLY, EXTENDED	EACH	10	1		1	1	1	1	1	1	1								
#	86400100	TRANSCEIVER - FIBER OPTIC	EACH	14	5		1	1	1	1	1	1	1								
#	87601100	PEDESTRIAN PUSH-BUTTON POST, GALVANIZED STEEL, TYPE I	EACH	6				3		2			1								
#	87900200	DRILL EXISTING HANDHOLE	EACH	3										3							
* #	88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	33			5	4	3	4	4	4		5							
* #	88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	72			7	16	7	8	8	6	8	6	6						
* #	88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	39			1	8	6	2	2	4	2	10	4						
* #	88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	24			1		4	2	2	4	2	5	4						
* #	88102810	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	8							8										
* #	88102825	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	60			6	8	8	8		8	6	8	8						
#	88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	168			14	28	20	16	16	18	16	21	19						
* #	88500100	INDUCTIVE LOOP DETECTOR	EACH	127	8		8	28	10	12	9	12	11	16	13						
#	88700200	LIGHT DETECTOR	EACH	35												35					
#	88700300	LIGHT DETECTOR AMPLIFIER	EACH	9												9					
#	88800100	PEDESTRIAN PUSH-BUTTON	EACH	76			6	16	8	8	8	8	6	8	8						
#	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	9	9																
* #	89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	2	2																
* #	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	10	1		1	1	1	1	1	1	1	1	1						
* #	89502380	REMOVE EXISTING HANDHOLE	EACH	69	3		3	12	6	6	12	4	9	8	2		4				
* #	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	68			5	9	10	5	8	5	7	10	9						
#	M2010110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1,346	1346																

- SEE SPECIAL PROVISIONS
- SPECIALTY ITEM

CONTINUED NEXT SHEET

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
BDD	9/1/11	
		SUMMARY OF QUANTITIES
		DRAWN BY
		CHECKED BY
		DATE

FILE: #FILE#
PLOTTED: 9/1/2011

HMG JOB NO. 5122