

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(5CS,13C,108,109)R	KENDALL	931	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SPEC. PROV. SPECIALTY ITEM	CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	FEDERAL = 80%				FEDERAL = 80%					FEDERAL=80%	FEDERAL=80%	FEDERAL = 0%			
					STATE = 20%				STATE = 10%					STATE=0%	STATE=0%	STATE = 0%			
					CITY=0%				CITY = 10%					CITY=20%	CITY=20%	CITY = 100%			
					ROADWAY	FOX RIVER BRIDGE REHABILITATION	IL 126 TRAFFIC SIGNALS	US 34 TRAFFIC SIGNALS	FOUNTAINVIEW DRIVE TRAFFIC SIGNALS	FOX STREET TRAFFIC SIGNALS	VAN EMMON STREET TRAFFIC SIGNALS	SOMONAUK STREET TRAFFIC SIGNALS	LANDMARK AVENUE TRAFFIC SIGNALS	COUNTRYSIDE PARKWAY TRAFFIC SIGNALS	CENTER PARKWAY TRAFFIC SIGNALS	SIDEWALK AND TRAIL REPL.	SIGNAL PRE-EMPTION (DISTRICT 1 CMAP)	ROADWAY (SOMONAUK STREET)	SAFETY AND LIGHTING
0003	0014	0021		0021					0028	0021	0003	0021	0031	0043					
	M2010210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1,548	1548														
	M2011000	TEMPORARY FENCE	METER	24	24														
*	M2011400	NITROGEN FERTILIZER NUTRIENT	KG	1	1														
*	M2011500	PHOSPHORUS FERTILIZER NUTRIENT	KG	1	1														
*	M2011600	POTASSIUM FERTILIZER NUTRIENT	KG	1	1														
	M2020010	EARTH EXCAVATION	CU M	86,200	86,200														
#	M2020020	ROCK EXCAVATION	CU M	404	400					4									
*	M2020050	EARTH EXCAVATION (WIDENING)	CU M	1,181	1181														
	M2080150	TRENCH BACKFILL	CU M	24,153	18642											21		5490	
	M2090110	POROUS GRANULAR BACKFILL	CU M	8	8														
	M2113100	TOPSOIL FURNISH AND PLACE, 100MM	SQ M	65,969	65,969														
	M2113600	TOPSOIL FURNISH AND PLACE, 600MM	SQ M	1,163	1163														
*	M2130201	EXPLORATION TRENCH 2.1 METER DEPTH	METER	67														67	
*	M2500100	SEEDING, CLASS 1	HA	6.0	6.0														
*	M2500210	SEEDING, CLASS 2A	HA	0.5													0.5		
*	M2500400	NITROGEN FERTILIZER NUTRIENT	KG	648	648														
*	M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	648	648														
*	M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	648	648														
*	M2510630	EROSION CONTROL BLANKET	SQ M	64,806	64,806														
*	M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	713	713														
*	M2800305	TEMPORARY DITCH CHECKS	METER	273.0	273.0														
	M2800400	PERIMETER EROSION BARRIER	METER	5,725	5725														
	M2800800	MULCH, METHOD 2	HA	6.5	6.5														

- SEE SPECIAL PROVISIONS
- SPECIALTY ITEM

CONTINUED NEXT SHEET

REVISIONS	
NAME	DATE
BDD	9/1/11

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 DATE _____ DRAWN BY _____
 CHECKED BY _____

FILE: \$FILE\$
 PLOTTED: 9/1/2011