

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(5CS,13C,108,109)R	KENDALL	931	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SPEC. PROV. SPECIALTY ITEM	CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	FEDERAL = 80%		FEDERAL = 80%							FEDERAL=80%	FEDERAL= 80%	FEDERAL = 0%			
					STATE = 20%		STATE = 10%							STATE=0%	STATE=0%	STATE = 0%			
					CITY=0%		CITY = 10%							CITY=20%	CITY= 20%	CITY = 100%			
					ROADWAY	FOX RIVER BRIDGE REHABILITATION	IL 126 TRAFFIC SIGNALS	US 34 TRAFFIC SIGNALS	FOUNTAINVIEW DRIVE TRAFFIC SIGNALS	FOX STREET TRAFFIC SIGNALS	VAN EMMON STREET TRAFFIC SIGNALS	SOMONAUK STREET TRAFFIC SIGNALS	LANDMARK AVENUE TRAFFIC SIGNALS	COUNTRYSIDE PARKWAY TRAFFIC SIGNALS	CENTER PARKWAY TRAFFIC SIGNALS	SIDEWALK AND TRAIL REPL.	SIGNAL PRE-EMPTION (DISTRICT 1 CMAP)	ROADWAY (SOMONAUK STREET)	SAFETY AND LIGHTING
0003	0014	0021		0021							0028	0021	0003	0021	0031	0043			
	M2810109	STONE RIPRAP, CLASS A5	SQ M	219	219														
	M2820200	FILTER FABRIC	SQ M	219	219														
	M3112010	SUB-BASE GRANULAR MATERIAL, TYPE C	M TON	459	459														
	M3510100	AGGREGATE BASE COURSE, TYPE A 100MM	SQ M	9,158	8874											284			
	M3510200	AGGREGATE BASE COURSE, TYPE A 200MM	SQ M	2,266	2266														
	M3511150	AGGREGATE BASE COURSE, TYPE B 150MM	SQ M	11,521	766								10,755						
	M3540200	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 200MM	SQ M	94												94			
	M3550415	HOT-MIX ASPHALT BASE COURSE, 115MM	SQ M	2,038	1927											111			
	M3560570	HOT-MIX ASPHALT BASE COURSE WIDENING, 270MM	SQ M	783	783														
*	M4021200	AGGREGATE FOR TEMPORARY ACCESS	M TON	4,161	4161														
*	M4060100	BITUMINOUS MATERIALS (PRIME COAT)	LITER	10,812	6799								3,424			589			
	M4060300	AGGREGATE (PRIME COAT)	M TON	19	16											3			
	M4060982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ M	146	109											37			
	M4060990	TEMPORARY RAMP	SQ M	976	921											55			
	M4062325	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	M TON	298	230											68			
	M4063305	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N30	M TON	1,610	107								1,503						
	M4063345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	M TON	449	363											86			
	M4063370	HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	M TON	250	250														
*	M4080100	BITUMINOUS MATERIALS (PRIME COAT)	LITER	3,956	3875											81			
	M4080300	AGGREGATE (PRIME COAT)	M TON	4.2	4.2														
	M4080500	INCIDENTAL HOT-MIX ASPHALT SURFACING	M TON	610	597											13			
	M4202255	PORTLAND CEMENT CONCRETE PAVEMENT 250MM (JOINTED)	SQ M	129,099	128411											688			
	M4205100	PAVEMENT FABRIC	SQ M	1,181	1181														
	M4230150	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 150MM	SQ M	2125	1839											286			
	M4230200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 200MM	SQ M	5474	5474														

- SEE SPECIAL PROVISIONS
- SPECIALTY ITEM

CONTINUED NEXT SHEET

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES

DATE _____ DRAWN BY _____ CHECKED BY _____

FILE: \$FILE\$
PLOTTED: 9/1/2011

HMG JOB NO. 5122