

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(5CS,13C,108,109)R	KENDALL	931	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

SPEC. PROV. SPECIALTY ITEM	CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	FEDERAL = 80% STATE = 20% CITY=0%				FEDERAL = 80% STATE = 10% CITY = 10%						FEDERAL=80%	FEDERAL=100%	FEDERAL = 0%				
					ROADWAY	FOX RIVER BRIDGE REHABILITATION	IL 126 TRAFFIC SIGNALS	US 34 TRAFFIC SIGNALS	FOUNTAINVIEW DRIVE TRAFFIC SIGNALS	FOX STREET TRAFFIC SIGNALS	VAN EMMON STREET TRAFFIC SIGNALS	SOMONAUK STREET TRAFFIC SIGNALS	LANDMARK AVENUE TRAFFIC SIGNALS	COUNTRYSIDE PARKWAY TRAFFIC SIGNALS	CENTER PARKWAY TRAFFIC SIGNALS	SIDEWALK AND TRAIL REPL.	SIGNAL PRE-EMPTION (DISTRICT 1 CMAP)	ROADWAY (SOMONAUK STREET)	SAFETY AND LIGHTING	STREETSCAPE ENHANCEMENTS	UTILITIES
					0003	0014	0021		0021						0028	0021	0003	0021	0031	0043	
*	M5030290	FORM LINER TEXTURED SURFACE	SQ M	3.4														3.4			
	M5030360	CONCRETE SUPERSTRUCTURE	CU M	11.1		11.1															
	M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	970		970															
*	M5090540	PIPE HANDRAIL	METER	54.2	54.2																
	M5200225	PREFORMED JOINT STRIP SEAL	METER	45		45															
	M542C656	REINFORCED CONCRETE PIPE TEE, 1350MM PIPE WITH 900MM RISER	EACH	1	1																
*	MX601315	DROP MANHOLE, TYPE A, SPECIAL	EACH	1														1			
	M542E112	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 300MM	EACH	9	9																
	M542E116	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 375MM	EACH	2	2																
	M542E120	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 450MM	EACH	6	6																
	M542F252	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 1200MM	EACH	2	2																
	M542H025	PIPE CULVERTS, CLASS A, TYPE 1 375MM	METER	20.5	20.5																
	M542H030	PIPE CULVERTS, CLASS A, TYPE 1 450MM	METER	9.5	9.5																
	M5500215	STORM SEWERS, CLASS B, TYPE 1 150MM	METER	6	6																
	M5500300	STORM SEWERS, CLASS B, TYPE 1 1200MM	METER	80.0	80																
	M5505530	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 300MM	METER	2,734.0	2,702.4											7.5		24.1			
	M5505550	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 450MM	METER	442.0	433.5											8.5					
	M5505570	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 600MM	METER	142.5	142.5																
	M5505590	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 750MM	METER	190.5	190.5																
	M5505610	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 900MM	METER	59.0	59.0																
	M5505620	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 1050MM	METER	137.0	137.0																
	M5505630	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 1200MM	METER	68.0	68.0																
	M5505640	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 1350MM	METER	243.0	243.0																
	M5505930	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 300MM	METER	1255.0	1,244.1											0.8		10.1			
	M5505950	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 450MM	METER	830.0	791.0											39.0					

- SEE SPECIAL PROVISIONS
- SPECIALTY ITEM

CONTINUED NEXT SHEET

REVISIONS	
NAME	DATE
BDD	9/1/11

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 DRAWN BY
 CHECKED BY
 DATE

FILE: \$FILE\$
 PLOTTED: 9/1/2011

HMG JOB NO. 5122