

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(5CS,13C,108,109R)	KENDALL	931	15
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

SPEC. PROV.	SPECIALTY ITEM	CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	FEDERAL = 80%				FEDERAL = 80%				FEDERAL=80%	FEDERAL = 0%			
						STATE = 20%				STATE = 10%				STATE=0%	STATE = 0%			
						CITY=0%				CITY = 10%				CITY=20%	CITY = 100%			
						ROADWAY	FOX RIVER BRIDGE REHABILITATION	IL 126 TRAFFIC SIGNALS	US 34 TRAFFIC SIGNALS	FOUNTAINVIEW DRIVE TRAFFIC SIGNALS	FOX STREET TRAFFIC SIGNALS	VAN EMMON STREET TRAFFIC SIGNALS	SOMONAUK STREET TRAFFIC SIGNALS	LANDMARK AVENUE TRAFFIC SIGNALS	COUNTRYSIDE PARKWAY TRAFFIC SIGNALS	CENTER PARKWAY TRAFFIC SIGNALS	SIDEWALK AND TRAIL REPL.	SIGNAL PRE-EMPTION (DISTRICT 1 CMAP)
0003	0014	0021		0021						0028	0021	0003	0021	0031	0043			
01	01	01	01	03	04	05	06	07	08	09	01	10	01	01	01	01		
		M7030550	PAVEMENT MARKING TAPE, TYPE III 200MM	METER	5,878	5878												
		M7030560	PAVEMENT MARKING TAPE, TYPE III 300MM	METER	1,234	1234												
		M7030580	PAVEMENT MARKING TAPE, TYPE III 600MM	METER	1,133	1133												
*		M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ M	13,811	13,811												
		M7040100	TEMPORARY CONCRETE BARRIER	METER	666	666												
		M7040200	RELOCATE TEMPORARY CONCRETE BARRIER	METER	446	446												
		M7200100	SIGN PANEL - TYPE 1	SQ M	140.82	122.71	0.45	1.1	1.8	0.9	2.7	1.8	0.9	1.8	4	2.66		
		M7200200	SIGN PANEL - TYPE 2	SQ M	70.72	23.22	5.4	5.4	5.4	4.5	5.4	5.4	5.4	5.4	5.2			
		M7280100	TELESCOPING STEEL SIGN SUPPORT	METER	64.3	64.3												
		M7300100	WOOD SIGN SUPPORT	METER	845.2	789.1								56.1				
*		M8100230	CONDUIT IN TRENCH, 25MM DIA., PVC	METER	1,464		59	374	167	164	48	227	95	221	109			
*		M8100240	CONDUIT IN TRENCH, 30MM DIA., PVC	METER	109		80	29										
*		M8100260	CONDUIT IN TRENCH, 50MM DIA., PVC	METER	4,834	2973	277	232	282	143	181	159	170	210	207			
*		M8100270	CONDUIT IN TRENCH, 65MM DIA., PVC	METER	15		3				2	3	2	4	1			
*		M8100280	CONDUIT IN TRENCH, 75MM DIA., PVC	METER	75		5	9	6			21		28	6			
*		M8100300	CONDUIT IN TRENCH, 100MM DIA., PVC	METER	454	2	62	80	50	29	25	33	65	70	38			
*		M8100540	CONDUIT IN TRENCH, 50MM DIA., COILABLE NONMETALLIC CONDUIT	METER	2,541												2541	
*	*	M8101020	CONDUIT PUSHED, 25MM DIA., GALVANIZED STEEL	METER	25		25											
*	*	M8101050	CONDUIT PUSHED, 50MM DIA., GALVANIZED STEEL	METER	925	738	34	82			14	38	19					
*	*	M8101070	CONDUIT PUSHED, 75MM DIA., GALVANIZED STEEL	METER	57		57											
*	*	M8101090	CONDUIT PUSHED, 100MM DIA., GALVANIZED STEEL	METER	774		85	138	80	84	61	73	58	104	91			
*	*	M8170020	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	METER	5,578		634	906	600	519	408	543	576	792	600			
*	*	M8170040	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	METER	13,811	5079	263	1120	1731	1091	691	606	821	682	1044	683		
		M8190200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	9,235	2975	80	403	727	505	331	252	443	332	533	359	2295	

• SEE SPECIAL PROVISIONS

CONTINUED NEXT SHEET

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES
		DRAWN BY
		CHECKED BY
		DATE

FILE: 9FILE\$
PLOTTED: 9/1/2011

HMG JOB NO. 5122