

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(SCS,13C,108,109)R	KENDALL	931	64
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

STORM SEWER REMOVAL SCHEDULE

LOCATION						COMMENTS	STORM SEWER REMOVAL										STORM SEWER TO BE ABANDONED					FILLING MANHOLES	REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS		
STATION	METER	LT/RT	STATION	METER	LT/RT		100MM METER	150MM METER	200MM METER	250MM METER	300MM METER	375MM METER	450MM METER	600MM METER	750MM METER	900MM METER	1350MM METER	300MM METER	375MM METER	450MM METER	525MM METER	900MM METER	EACH	EACH	EACH	EACH	
IL RTE 47																											
18+452.800	10.2	RT	18+490.890	8.6	RT									37.8													
			18+490.393	12.5	LT	CB ONLY / PIPE NOT FOUND																			1		
18+490.411	10.0	RT	18+490.747	9.0	RT					0.9																	1
18+491.262	8.6	RT	18+558.783	10.6	RT									67.5													1
18+538.434	13.4	RT	18+558.786	10.7	RT	CMP / FES INLET						20.5															1
18+559.543	10.7	RT	18+596.504	14.0	RT										37.1												1
18+597.264	14.0	RT	18+631.144	15.0	RT										33.9												1
18+618.906	15.3	LT	18+630.979	15.1	LT								12.5														1
18+623.326	25.8	RT	18+623.351	17.0	RT	PVC			8.8																		
18+623.480	16.6	RT	18+631.151	15.1	RT	PVC			7.8																		1
18+630.044	16.9	LT	18+631.070	15.6	LT	PVC				1.3																	1
18+631.337	14.9	LT	18+631.483	12.7	LT								2.6														1
18+631.635	15.1	LT	18+654.363	14.8	LT								20														1
18+631.906	15.0	RT	18+677.184	13.7	RT										45.3												1
18+677.550	19.7	RT	18+677.552	14.1	RT	PARTIAL REMOVAL						5.6															1
18+677.946	13.7	RT	18+766.432	13.6	RT										88.5												1
18+758.309	15.4	RT	18+766.440	13.7	RT	PVC		8.3																			1
18+767.194	13.6	RT	18+792.703	14.2	RT										29.5												1
19+585.000	20.9	RT	19+610.500	20.6	RT	PARTIAL REMOVAL				25.5																	1
19+610.692	20.3	RT	19+611.472	18.6	RT	FES OUTLET				1.8																	1
19+742.896	17.6	RT	19+743.920	14.9	RT	FES OUTLET / PARTIAL REMOVAL					3																1
19+988.812	14.4	RT	19+989.902	20.3	RT	CONC							6														1
19+993.006	10.6	RT	20+079.797	7.9	RT						85.9																1
19+993.606	11.8	RT	20+011.098	15.9	RT	CMP / PARTIAL REMOVAL						18															1
20+080.479	8.1	RT	20+087.458	13.7	RT						8.9																1
20+080.987	38.1	RT	20+087.652	14.3	RT						24.5																1
20+141.174	31.3	RT	20+141.174	31.3	RT																						1
20+304.932	6.5	RT	20+310.466	7.9	RT							5.7															1
20+304.932	6.4	RT	20+307.243	6.5	RT					2.3																	1
20+311.217	7.9	RT	20+343.184	7.6	RT							32															1
20+341.456	25.9	LT	20+342.177	9.9	LT	CONC				16																	1
20+341.808	26.3	LT	20+350.669	27.8	LT	CONC				9																	1
20+343.603	7.2	RT	20+343.672	6.6	RT							0.7															1
20+343.824	7.9	RT	20+345.438	9.6	RT							2.4															1
20+345.763	10.3	RT	20+350.829	39.0	RT	PARTIAL REMOVAL						29.2															1
20+444.587	29.7	LT	20+446.456	15.8	LT	PVC / PARTIAL REMOVAL				14																	1
20+446.636	15.3	LT	20+463.486	7.9	LT	CMP					18.3																1
20+458.533	15.2	LT	20+463.658	7.9	LT					8.9																	1
20+464.119	7.8	LT	20+500.950	7.6	LT	CORR. PLASTIC					36.7																1
20+501.264	6.0	LT	20+501.334	7.4	LT					1.4																	1
20+501.715	7.6	LT	20+530.445	9.0	LT	CMP					28.6																1
20+503.161	8.0	RT	20+503.525	6.0	RT					2																	1
20+503.472	8.4	RT	20+560.728	11.3	RT							57.6															1

CONTINUED ON NEXT SHEET

FILE: 064sch_rem_47.dgn
PLOTTED: 8/14/2011

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">SCHEDULE OF QUANTITIES</p> <p align="right">DRAWN BY CHECKED BY</p> <p>DATE</p>

HMG JOB NO. 5122