

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(5CS,13C,108,109R)	KENDALL	931	65
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

STORM SEWER REMOVAL SCHEDULE

LOCATION						STORM SEWER REMOVAL										STORM SEWER TO BE ABANDONED					FILLING MANHOLES	REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS			
STATION	METER	LT/RT	STATION	METER	LT/RT	COMMENTS	100MM METER	150MM METER	200MM METER	250MM METER	300MM METER	375MM METER	450MM METER	600MM METER	750MM METER	900MM METER	1350MM METER	300MM METER	375MM METER	450MM METER	525MM METER	900MM METER	EACH	EACH	EACH	EACH	
20+530.445	9.0	LT	20+556.592	9.9	LT	CMP / RCP						26.1															
20+549.669	6.1	LT	20+549.704	7.0	LT						1																1
20+557.349	10.0	LT	20+570.213	12.6	LT									13.1										1			1
20+561.131	10.9	RT	20+561.436	6.3	RT						4.7																1
20+561.485	11.3	RT	20+589.197	12.9	RT							27.9													1		
20+569.147	53.5	LT	20+569.644	45.4	LT	PARTIAL REMOVAL								8.1													
20+569.694	44.6	LT	20+571.850	12.9	LT									31.8													
20+570.576	12.6	LT	20+571.494	12.5	LT									0.9											1		
20+572.258	12.5	LT	20+588.016	11.5	LT						15.7																1
20+578.201	57.9	RT	20+578.201	57.9	RT																						1
20+583.693	37.8	LT	20+589.800	14.5	LT	CLAY				24.3																	1
20+588.884	31.4	LT	20+589.948	14.7	LT	CAST			16.3																		1
20+589.616	13.3	RT	20+590.396	20.5	RT	PARTIAL REMOVAL								7.4										1			
20+590.138	14.1	LT	20+593.239	10.1	LT	CAST				5																	1
20+642.825	8.4	LT	20+646.394	13.6	RT	CMP								22.3													1
20+642.909	8.7	LT	20+646.674	13.2	LT	PVC		5.9																			1
20+646.473	13.6	RT	20+650.341	8.0	RT	CMP					6.8																1
20+734.378	21.8	LT	20+744.818	11.6	LT	CLAY					14.6																1
20+744.298	40.3	LT	20+747.015	39.8	LT	CLAY				2.8																	1
20+745.334	11.1	LT	20+749.076	10.5	LT	CLAY					3.8																1
20+747.271	39.8	LT	20+756.068	37.8	LT	PVC					9																1
20+749.226	10.1	LT	20+749.403	7.1	LT	CLAY					3																1
20+756.443	38.1	LT	20+756.595	53.2	LT					15.2																	1
20+756.453	37.3	LT	20+756.793	28.1	LT	CMP			9.3																1		
20+818.123	7.5	LT	20+818.137	8.2	LT	CLAY						0.7															1
20+818.137	8.2	LT	20+823.263	8.1	LT	CLAY						5.1															1
20+818.928	7.4	RT	20+819.020	2.7	RT	CLAY					4.7																1
20+819.298	7.5	RT	20+824.581	7.8	RT	CLAY					5.3																1
20+819.313	6.6	LT	20+823.286	8.0	LT	PLASTIC	4.2																				1
20+823.676	7.8	LT	20+824.929	7.5	RT	CLAY						15.3												1			
20+825.108	8.2	RT	20+837.195	37.0	RT	CLAY / PARTIAL REMOVAL						31.2															1
20+825.859	9.5	LT	20+825.874	13.4	LT	CLAY				3.8																	1
20+826.002	13.7	LT	20+836.845	13.9	LT	CLAY				10.8																	1
20+925.511	8.0	LT	20+928.298	6.1	RT								14.5														1
20+926.509	8.2	RT	20+928.088	6.8	RT	PVC			2.1																		1
20+928.752	6.5	RT	20+944.026	6.5	RT	CLAY											15.1										1
20+938.368	19.2	LT	20+945.608	9.1	LT						12.5																1
20+944.535	6.8	RT	20+948.946	19.3	RT	CLAY / RCP						13.2															1
20+948.946	19.3	RT	20+950.898	24.7	RT	CLAY / RCP													5.6								1
20+944.790	6.5	RT	20+952.829	8.1	RT						8.1																1
20+946.070	9.0	LT	20+950.945	8.9	LT						5																1
20+951.335	24.8	RT	21+002.201	22.9	RT	FES OUTLET						51.7															1
20+951.694	9.0	LT	20+956.534	10.4	LT						5.1																2
21+000.096	20.7	RT	21+003.717	20.3	RT	FES OUTLET					3.6																1

CONTINUED ON NEXT SHEET

FILE: 064sch_rem_47.dgn
PLOTTED: 8/14/2011

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES
		DRAWN BY
		CHECKED BY
		DATE

HMG JOB NO. 5122