

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(5CS,13C,108,109)R	KENDALL	931	68
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

STORM SEWER REMOVAL SCHEDULE

LOCATION						STORM SEWER REMOVAL										STORM SEWER TO BE ABANDONED					FILLING MANHOLES	REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS					
STATION	METER	LT/RT	STATION	METER	LT/RT	COMMENTS	100MM METER	150MM METER	200MM METER	250MM METER	300MM METER	375MM METER	450MM METER	600MM METER	750MM METER	900MM METER	1350MM METER	300MM METER	375MM METER	450MM METER	525MM METER	900MM METER	EACH	EACH	EACH	EACH			
189+213.234	13.1	LT	189+325.872	11.2	LT	CMP / RCP										112.3									1				
189+253.807	12.7	LT	189+253.810	11.7	LT	RCP						1													1				
189+326.638	11.2	LT	189+501.652	13.0	LT									174											1				
189+502.312	12.7	LT	189+503.224	11.9	LT	PARTIAL REMOVAL										1.2													
189+573.178	8.0	LT	189+638.481	8.2	LT																65.3								
189+641.487	8.2	LT	189+802.758	8.7	LT																161.3	1							
189+745.373	10.8	RT	189+745.472	7.8	RT	FES OUTLET				3.0																		1	
189+746.315	11.8	LT	189+746.393	10.6	LT	FES OUTLET				1.3																		1	
189+803.140	9.1	LT	189+803.159	14.3	LT													5.2										1	
189+803.286	14.3	LT	189+806.649	10.9	LT						4.7																	1	
189+803.520	8.7	LT	189+890.554	7.8	LT																87	1						1	
189+806.411	11.0	RT	189+806.452	9.9	RT	FES OUTLET				1.1																		1	
189+891.138	8.2	LT	189+894.298	13.2	LT																6				1				
189+894.496	13.9	LT	189+894.361	24.4	LT					10.5																		1	
189+894.797	13.3	LT	189+897.737	10.9	LT					3.8																		1	
189+894.500	13.1	LT	189+894.457	10.1	RT					23.3																		1	
189+894.884	13.5	LT	189+970.375	12.8	LT											75.2												1	
189+934.676	9.5	LT	189+938.541	13.3	LT					5.4																		1	
190+047.109	22.9	LT	190+046.360	19.5	LT					3.2																		1	
190+046.225	19.5	LT	190+046.730	10.6	LT					8.8																		1	
190+046.790	9.9	LT	190+047.828	9.9	RT	CMP / RCP				19.8																		1	
190+047.137	10.3	LT	190+132.417	10.2	LT	PARTIAL REMOVAL				85.1																		1	
190+132.810	9.8	LT	190+133.303	14.0	RT	FES INLET				23.8																		1	
190+133.105	10.4	LT	190+138.883	14.6	LT	CMP			7.2																			1	
190+133.176	10.2	LT	190+171.736	14.1	LT	CMP / FES INLET				38.8																		1	
190+176.732	18.6	LT	190+176.770	14.7	LT	PLASTIC				3.9																		1	
190+176.726	22.0	LT	190+176.730	18.9	LT	PLASTIC / PARTIAL REMOVAL				3.1																		1	
SOMONAUK ST																													
1+018.482	3.4	LT	1+075.112	1.9	LT							56.1																1	
1+075.873	1.9	LT	1+092.090	1.0	LT							16.2																1	
TOTAL							6.7	19.3	53.6	78.7	1142.2	658.9	405.9	153.5	333.8	462.1	2.1	49.5	80.8	15.1	39.1	319.6	2	66	16	87			
ROUNDED							7	20	54	79	1143	659	406	154	334	463	6	50	81	16	40	320	2	66	16	87			

FILE: 054sch_rem_47.dgn
PLOTTED: 8/14/2011

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
DATE		DRAWN BY
		CHECKED BY

SCHEDULE OF QUANTITIES

HMG JOB NO. 5122