

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(5CS,13C,108,109)R	KENDALL	931	70
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

**DRIVEWAY PAVEMENT REMOVAL SCHEDULE**

LOCATION		DRIVEWAY PAVEMENT REMOVAL
STATION	LT / RT	SQ M
<b>IL RTE 47</b>		
18+543.8	RT	70.03
18+617.5	RT	198.22
19+328.6	RT	221.10
19+357.6	LT	164.96
19+524.8	LT	114.50
19+630.4	LT	184.99
19+681.9	LT	146.37
19+822.6	LT	203.86
19+895.6	RT	235.07
19+948.3	RT	78.35
19+975.9	RT	116.46
20+122.1	LT	192.43
20+143.6	LT	102.73
20+202.4	RT	93.13
20+230.3	RT	283.88
20+280.2	LT	50.10
20+281.5	RT	165.98
20+320.0	RT	300.65
20+384.2	LT	73.77
20+418.8	RT	47.18
20+509.4	LT	158.57
20+617.1	LT	706.08
20+625.3	RT	225.75
20+658.2	RT	119.91
20+687.3	RT	104.17
20+755.9	RT	203.78
21+217.1	LT	25.19
21+219.3	RT	46.46
21+395 & 21+423.5	RT	597.98
21+512.5	RT	58.04
21+531.3	LT	78.83
21+533.0	RT	61.84
21+557.1	LT	79.95
21+635.8	RT	28.01
21+647.6	RT	26.48
21+739.9	RT	63.93
21+758.4	LT	16.53
21+800.5	LT	90.69
21+823.5	LT	55.00
21+866.0	LT	104.44
21+876.5	LT	102.13
21+951.5	RT	580.40
21+991.6	RT	63.10
22+014.1	LT	200.95
22+046.1	LT	82.10
22+073.3	RT	77.76
22+084.1	LT	158.34
22+105.4	RT	99.53
22+125.4	LT	137.63
22+273.6	LT	60.21
22+349.1	LT	67.34
22+363.4	LT	91.45
22+413.5	LT	92.33
22+509.8	LT	126.50
22+526.2	RT	141.11
22+572.5	LT	257.53
22+605.6	RT	157.33
22+626.8	LT	272.12
22+747.5	RT	123.33
22+771.8	LT	269.77
22+807.8	RT	117.97
22+819.4	LT	233.11

LOCATION		DRIVEWAY PAVEMENT REMOVAL
STATION	LT / RT	SQ M
22+846.9	RT	100.59
23+048.9	LT	201.90
23+611.5	LT	201.55
<b>IL RTE 126</b>		
50+037.5	LT	138.93
<b>US RTE 34</b>		
189+801.1	LT	145.86
189+827.8	LT	92.70
189+861.2	LT	99.31
189+885.5	LT	126.09
189+891.4	RT	155.70
189+914.8	LT	37.60
190+065.2	LT	119.64
190+098.8	LT	274.59
190+112.5	LT	120.08
190+156.0	LT	401.90
190+225.3	RT	55.41
190+276.8	LT	49.16
190+317.3	LT	49.00
190+318.0	RT	213.48
<b>ELIZABETH ST.</b>		
1+071.4	RT	247.72
<b>FOX ST.</b>		
7+907.5	LT	74.04
7+939.9	LT	99.00
7+971.0	RT	292.15
7+975.8	LT	202.18
8+026.8	RT	103.51
8+047.9	RT	28.55
8+072.8	RT	31.85
8+081.2	LT	42.12
8+100.2	RT	9.40
<b>JEFFERSON ST.</b>		
1+088.4	RT	138.46
1+120.5	RT	91.61
<b>VAN EMMON ST.</b>		
1+030.6	LT	17.60
1+048.5	LT.	14.11
<b>HYDRAULIC AVE.</b>		
1+130.0	LT.	464.59
<b>SPRING ST.</b>		
1+065.2	RT.	75.15
<b>SOMONAUK ST.</b>		
1+011.9	LT	15.50
1+026.5	RT	11.13
1+034.2	RT	20.57
1+036.6	LT	50.75
1+046.0	LT	62.50
1+071.8	LT	59.63
1+161.6	LT	31.43

LOCATION		DRIVEWAY PAVEMENT REMOVAL
STATION	LT / RT	SQ M
<b>APPLETREE CT.</b>		
1+068.2	LT	13.04
1+075.0	LT	18.04
1+078.8	RT	167.53
1+085.6	LT	131.99
TOTAL		14505.06
ROUNDED		14505

**PAVEMENT REMOVAL SCHEDULE**

LOCATION		PAVEMENT REMOVAL
STATION	STATION	SQ M
<b>IL RTE 47</b>		
18+480.0	TO 18+625.0	2920.8
18+625.0	TO 18+800.0	3744.1
18+800.0	TO 18+975.0	3173.7
18+975.0	TO 19+150.0	3347.9
19+150.0	TO 19+325.0	2363.2
19+325.0	TO 19+500.0	3146.7
19+500.0	TO 19+675.0	3073.8
19+675.0	TO 19+850.0	2943.8
19+850.0	TO 20+025.0	2941.1
20+025.0	TO 20+200.0	2978.1
20+200.0	TO 20+375.0	2439.0
20+375.0	TO 20+550.0	2304.0
20+550.0	TO 20+725.0	3010.0
20+725.0	TO 20+900.0	4010.3
20+900.0	TO 20+928.1	494.7
20+933.0	TO 20+984.0	995.9
21+204.0	TO 21+375.0	3257.1
21+375.0	TO 21+550.0	2180.8
21+550.0	TO 21+725.0	3314.5
21+725.0	TO 21+900.0	1871.0
21+900.0	TO 22+075.0	2025.8
22+075.0	TO 22+250.0	2742.2
22+250.0	TO 22+425.0	3842.9
22+425.0	TO 22+600.0	3785.4
22+600.0	TO 22+775.0	4886.2
22+775.0	TO 22+950.0	3750.2
22+950.0	TO 23+125.0	3033.3
23+125.0	TO 23+300.0	4682.6
23+300.0	TO 23+475.0	3175.6
23+475.0	TO 23+650.0	3271.0
23+650.0	TO 23+715.0	106.3
<b>IL RTE 126</b>		
50+050.0	TO 50+175.0	603.4
<b>US RTE 34</b>		
189+677.0	TO 189+775.0	1756.5
189+775.0	TO 189+950.0	3430.0
190+040.0	TO 190+125.0	1480.9
190+125.0	TO 190+300.0	2781.9
190+300.0	TO 190+410.0	661.9
<b>FOX ST</b>		
7+892.3	TO 7+970.0	572.5
8+030.0	TO 8+102.5	625.7
<b>JEFFERSON ST</b>		
1+018.6	TO 1+130.5	286.6
<b>SOMONAUK ST</b>		
1+048.5	TO 1+064.6	120.8
1+134.8	TO 1+185.0	371.9
1+185.0	TO 1+214.0	61.1
<b>COUNTRYSIDE PKWY</b>		
1+091.0	TO 1+155.0	86.0
TOTAL		102,651.2
ROUNDED		102,652

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center"><b>SCHEDULE OF QUANTITIES</b></p> <p align="right">DRAWN BY _____</p> <p align="right">CHECKED BY _____</p> <p>DATE _____</p>

FILE: 064sch\_r\_en\_47.dgn  
PLOTTED: 8/14/2011

HMG JOB NO. 5122