

PROPOSED CURB AND GUTTER SCHEDULE

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(5CS,13C,108,109R)	KENDALL	931	83
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

LOCATION		CONCRETE CURB, TYPE B (SPECIAL)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30 (ABUTTING EXISTING)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60 (ABUTTING EXISTING)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30 (DOWELLED)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.45 (DOWELLED)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60 (DOWELLED)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B (SPECIAL)	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-10.30 (DOWELLED)
STATION	STATION	LT/RT	METER	METER	METER	METER	METER	METER	METER	METER
FOUNTAIN VILLAGE										
0+971.300	TO 0+986.200	RT					20.40			
0+971.300	TO 0+986.200	LT					22.50			
FOUNTAIN VIEW										
		LT					16.50			
		RT						12.20		
GREENBRIAR										
1+155.000	TO 1+174.514	RT				19.60				
1+155.000	TO 1+189.621	LT						45.40		
1+174.514	TO 1+184.934	RT						13.20		
GARDEN										
1+167.000	TO 1+173.219	RT				6.30				
1+167.000	TO 1+189.457	LT						36.70		
1+173.219	TO 1+186.998	RT						18.40		
BEAVER										
1+010.196	TO 1+024.596	LT						22.70		
1+013.806	TO 1+028.206	RT						22.70		
1+024.596	TO 1+039.000	LT				14.40				
1+028.206	TO 1+039.000	RT				10.80				
1+039.000	TO 1+050.000	RT		11.00						
COLONIAL										
1+005.780	TO 1+019.170	LT						17.10		
1+016.022	TO 1+027.704	RT						21.50		
1+019.170	TO 1+032.000	LT				12.60				
1+027.704	TO 1+032.000	RT				4.50				
ELIZABETH										
1+058.500	TO 1+089.885	RT						35.40		
1+058.500	TO 1+060.772	LT						2.30		
1+083.394	TO 1+089.885	LT						11.30		
MAIN ST S										
1+001.665	TO 1+025.154	LT						27.40		
1+004.419	TO 1+025.154	RT						24.50		
ORANGE ST										
1+068.500	TO 1+093.189	LT				31.50				
1+068.500	TO 1+086.596	RT						26.80		
1+106.595	TO 1+139.000	RT						40.10		
1+112.495	TO 1+139.000	LT				35.30				
WASHINGTON ST										
1+063.800	TO 1+092.464	LT				35.90				
1+063.500	TO 1+088.315	RT				33.20				
1+107.432	TO 1+125.000	RT				23.70				
1+111.533	TO 1+125.000	LT				21.60				
FOX ST										
7+892.414	TO 7+989.024	RT				106.30				
7+892.414	TO 7+991.976	LT				107.40				
8+007.827	TO 8+065.000	RT				64.70				
8+010.732	TO 8+048.082	LT				51.60				
8+056.082	TO 8+065.182	LT				13.00				
JEFFERSON ST										
1+018.500	TO 1+130.670	RT						113.50		
VAN EMMON ST										
1+031.500	TO 1+090.328	RT				66.70				
1+033.000	TO 1+090.862	LT				69.30				
1+109.037	TO 1+137.000	RT				33.20				
1+109.863	TO 1+136.396	LT				29.60				

CONTINUED ON NEXT SHEET

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		DATE
		DRAWN BY
		CHECKED BY

SCHEDULE OF QUANTITIES

FILE: 078sch_prop.dgn
PLOTTED: 8/14/2011

HMG JOB NO. 5122