

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(5CS,13C,108,109)R	KENDALL	931	86
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAVEMENT PATCHING AND CURB REPLACEMENT SCHEDULE

LOCATION				CLASS C PATCHES, TYPE IV, 200 MM	CLASS D PATCHES, TYPE IV, 150 MM	CLASS D PATCHES, TYPE IV, 300 MM	CURB REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	CONCRETE CURB, TYPE B	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60
STATION	TO	STATION	RT/LT	SQ M	SQ M	SQ M	METER	METER	METER	METER	METER
189+482	TO	189+500	LT	66.30				11.7		11.65	
189+541	TO	189+553	LT		41.5		12.7		12.7		
189+559	TO	189+570	LT		39.6		11.8		11.8		
189+637	TO	189+677	LT			93.5		12.1			12.10
TOTALS				66.30	81.10	93.50	24.50	23.80	24.5	11.65	12.1
TOTALS ROUNDED FOR SUMMARY SHEET				66	81	94	25	24	24.5	11.7	12.1

PROPOSED CROSSWALK SCHEDULE

LOCATION		CONCRETE COLOR ADDITIVE
STATION	LT/RT	CU M
IL 47		
20+329.6		9.6
20+821.0		12.0
20+831.0	RT	5.1
20+831.0	LT	4.8
20+838.0		12.2
20+938.4	LT	4.4
20+940.3	RT	6.3
20+947.1		8.8
21+360.8	LT	5.4
21+361.9	RT	8.9
21+370.5		18.6
21+481.4	LT	5.9
21+668.6		11.9
21+679.0	LT	8.4
21+685.3	RT	9.0
21+697.0		15.5
TOTAL		146.6
ROUNDED		146.6

PIPE UNDERDRAINS, 100MM SCHEDULE

LOCATION		PIPE UNDERDRAINS, 100MM	
STATION	LT/RT	METER	
IL RTE 47			
18+565.000	LT	14.9	
18+565.000	RT	11.3	
18+860.000	LT	14.0	
18+860.000	RT	10.3	
19+150.000	LT	15.4	
19+150.000	RT	15.2	
19+450.000	LT	35.7	
19+450.000	RT	18.2	
19+750.000	LT	21.2	
19+750.000	RT	21.2	
20+061.000	LT	9.8	
20+061.000	RT	9.8	
20+327.000	LT	11.4	
20+327.000	RT	12.1	
20+475.000	LT	12.3	
20+475.000	RT	12.1	
20+669.000	LT	10.5	
20+669.000	RT	10.7	
20+953.800	LT	8.9	
20+953.800	RT	11.7	
21+204.000	LT	12.9	
21+204.000	RT	12.4	
21+618.500	LT	9.8	
21+618.500	RT	9.8	
21+727.737	LT	9.8	
21+727.737	RT	9.8	
21+850.000	LT	28.5	
21+850.000	RT	28.5	
21+987.153	LT	9.8	
21+987.153	RT	9.8	
22+156.885	LT	9.8	
22+156.885	RT	9.8	
22+287.241	LT	9.8	
22+287.241	RT	9.8	
22+480.000	LT	18.5	
22+480.000	RT	11.3	
22+884.834	LT	13.4	
22+884.834	RT	15.9	
23+016.365	LT	14.3	
23+016.365	RT	10.1	
23+255.000	LT	13.7	
23+255.000	RT	10.1	
23+395.000	LT	10.1	
23+395.000	RT	10.1	
23+564.129	RT	10.1	
IL RTE 126			
50+024.077	LT	11.9	
50+024.471	RT	10.6	
TOTALS		753.3	
USE		753.5	

RETAINING WALLS SCHEDULE

LOCATION				SEGMENTAL CONCRETE BLOCK WALL	PCC SIDEWALK SPECIAL WITH RETAINING WALL	PIPE HANDRAIL
STATION	TO	STATION	RT/LT	SQ M	SQ M	METER
VAN EMMON STREET						
1+065.76	TO	1+082.5	RT		16.52	16.89
RIVER STREET						
1+068.81	TO	1+088.729	LT	28.74		
TOTALS				28.74	16.52	16.89
TOTALS ROUNDED FOR SUMMARY SHEET				28.7	16.5	16.9

PROPOSED ISLAND SCHEDULE SCHEDULE

LOCATION		CONCRETE ISLAND (SPECIAL)	PRISMATIC CURB REFLECTOR
STATION	LT/RT	SQ M	EACH
IL RTE 47			
18+508.2	LT	42.51	
18+835.2	LT	81.42	
20+104.0	RT	67.79	8
20+351.0	RT	25.69	8
22+264.0	RT	14.65	
22+527.0	RT	34.49	
22+604.0	RT	12.8	
22+686.0	RT	43.74	8
22+688.0	LT	53.38	8
22+717.0	RT	55.9	8
22+718.0	LT	47.14	8
22+771.8	LT	37.36	
22+807.0	RT	21.46	
23+436.5	RT	52.58	8
US RTE 34			
190+112.6	RT	13.41	
190+226.5	RT	20.24	
TOTALS		624.56	56
ROUNDED		625	56

TEMPORARY DRAINAGE ITEMS

LOCATION		TEMPORARY CATCH BASINS	TEMPORARY DRAINAGE CONNECTION
STATION	LT/RT	EACH	EACH
STAGE 1			
18+605.0	CTR	1	
18+965.0	CTR	1	
19+318.0	CTR	1	
20+073.0	RT		1
20+921.0	CTR	1	
21+346.0	CTR	1	
21+656.0	CTR	1	
STAGE 2			
20+061.0	CTR	1	
21+987.0	CTR	1	
22+156.9	CTR	1	
22+287.3	CTR	1	
STAGE 4			
189+972.5	LT		1
STAGE 6			
190+046.3	CTR	1	
190+305.0	CTR	1	
TOTALS		12	2

PIPE DRAINS SCHEDULE

LOCATION		PIPE DRAINS, 100MM	PIPE DRAINS, 150MM	PIPE DRAINS, 200MM
STATION	LT/RT	METER	METER	METER
IL RTE 47				
18+648.000	RT			26.5
19+772.500	RT	12.0		
22+402.000	LT		6.5	
TOTALS		12.0	6.5	26.5
USE		12.0	6.5	26.5

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">SCHEDULE OF QUANTITIES</p> <p align="right">DRAWN BY _____</p> <p align="right">CHECKED BY _____</p> <p align="right">DATE _____</p>