

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(SCS,13C,108,109)R	KENDALL	931	87
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PROPOSED SIDEWALK SCHEDULE

LOCATION				PORTLAND CEMENT CONCRETE SIDEWALK 100MM			CONCRETE COLOR ADDITIVE
				100% STATE	80% STATE / 20% CITY	100% CITY	100% CITY
STATION		STATION	LT/RT	SQ M	SQ M	SQ M	CU M
IL RTE 47							
18+489.5	TO	18+500.7	LT	16.46			
18+515.4	TO	18+712.1	LT	299.25			
18+703.2	TO	18+704.7	RT		7.61		
18+735.5	TO	18+824.1	LT	135.39			
18+734.1	TO	18+745.3	RT	25.53			
18+846.0	TO	18+858.6	LT	17.65			
18+910.5	TO	19+011.5	LT		150.29		
19+039.2	TO	19+352.1	LT		469.64		
19+356.1	TO	19+365.5	LT	15.00			
19+411.5	TO	19+416.6	LT	7.17			
19+434.4	TO	19+442.5	LT	11.43			
19+624.2	TO	19+625.7	LT	2.23			
19+635.1	TO	19+636.6	LT	2.18			
19+676.8	TO	19+678.3	LT	2.16			
19+685.5	TO	19+815.8	LT		199.11		
19+828.6	TO	19+953.0	LT		191.51		
19+965.2	TO	20+116.8	LT		231.16		
20+112.7	TO	20+194.5	RT		126.11		0.143
20+127.4	TO	20+138.2	LT		14.05		
20+148.8	TO	20+276.6	LT		189.96		
20+207.6	TO	20+225.4	RT		33.16		0.864
20+235.2	TO	20+276.6	RT		82.11		2.28
20+283.8	TO	20+336.7	LT		80.74		
20+286.4	TO	20+315.1	RT		55.25		1.512
20+324.9	TO	20+346.7	RT		50.14		1.196
20+355.0	TO	20+380.9	LT		37.07		
20+362.7	TO	20+411.1	RT		70.33		
20+387.5	TO	20+441.6	LT		80.81		
20+418.8	TO	20+445.6	RT		39.89		
20+461.0	TO	20+504.5	LT		66.07		0.149
20+464.6	TO	20+562.7	RT		148.75		
20+514.4	TO	20+557.0	LT		86.09		2.354
20+587.2	TO	20+606.3	RT	42.66			0.206
20+588.5	TO	20+633.9	LT	94.64			1.576
20+614.9	TO	20+633.5	RT	22.31			
20+643.7	TO	20+745.9	LT		154.52		0.237
20+644.1	TO	20+652.7	RT	10.83			
20+663.7	TO	20+682.0	RT		25.28		
20+692.6	TO	20+752.0	RT		86.80		
20+745.9	TO	20+821.2	LT	113.81			
20+759.8	TO	20+791.3	RT		46.08		
20+791.3	TO	20+821.0	RT	50.99			0.415
20+839.7	TO	20+843.7	LT	12.35			0.373
20+840.3	TO	20+849.5	RT	18.84			0.246
20+905.2	TO	20+926.7	LT	56.74			1.231
20+905.7	TO	20+906.5	RT	2.78			
20+920.0	TO	20+928.2	RT	21.75			0.584
20+932.5	TO	20+934.0	LT	1.81			
20+941.0	TO	20+993.2	LT	128.61			0.671
20+943.5	TO	20+997.1	RT	111.12			2.639
21+190.7	TO	21+214.7	LT	34.85			
21+194.8	TO	21+216.0	RT	40.76			0.984
21+219.6	TO	21+240.7	LT	29.77			
21+222.6	TO	21+356.9	RT	211.50			0.277
21+253.6	TO	21+355.2	LT	176.62			1.458
21+366.7	TO	21+374.0	LT	26.39			0.334
21+367.0	TO	21+391.1	RT	50.90			0.108
21+398.9	TO	21+422.9	RT	33.82			

CONTINUED

LOCATION				PORTLAND CEMENT CONCRETE SIDEWALK 100MM			CONCRETE COLOR ADDITIVE
				100% STATE	80% STATE / 20% CITY	100% CITY	100% CITY
STATION		STATION	LT/RT	SQ M	SQ M	SQ M	CU M
21+430.7	TO	21+472.6	RT	60.38			
21+467.8	TO	21+475.0	LT	14.83			
21+484.8	TO	21+521.5	LT	65.22			1.374
21+487.8	TO	21+512.6	RT		34.78		
21+517.9	TO	21+524.9	RT		8.36		
21+530.7	TO	21+553.1	LT	42.00			0.696
21+530.9	TO	21+582.9	RT		75.21		
21+561.1	TO	21+585.4	LT	35.89			
21+605.0	TO	21+632.5	RT		38.40		
21+607.9	TO	21+660.5	LT	77.16			
21+638.9	TO	21+644.3	RT		5.85		
21+650.7	TO	21+668.9	RT		26.14		
21+697.3	TO	21+699.8	LT	3.80			
21+699.8	TO	21+735.9	RT		54.09		
21+743.9	TO	21+803.2	RT		86.91		
21+809.1	TO	21+810.3	LT	9.83			
21+820.3	TO	21+949.2	RT		185.08		
21+861.9	TO	21+863.1	LT	1.95			
21+909.1	TO	21+910.7	LT	1.62			
21+957.7	TO	21+997.8	RT		55.79		
22+002.3	TO	22+069.1	RT		97.32		
22+077.5	TO	22+101.5	RT		33.75		
22+109.3	TO	22+205.5	RT		164.23		
22+217.4	TO	22+225.6	RT		21.40		
22+423.0	TO	22+521.1	RT		154.08		
22+429.2	TO	22+430.8	LT		7.87		
22+534.2	TO	22+598.6	RT		95.39		
22+609.0	TO	22+670.4	RT		90.74		
22+723.6	TO	22+741.2	RT		27.80		
22+752.5	TO	22+800.4	RT		73.65		
22+815.2	TO	22+841.6	RT		38.89		
22+852.2	TO	22+947.9	RT		143.23		
22+965.5	TO	22+984.2	RT	27.60			
23+034.3	TO	23+171.5	RT		203.44		
23+210.8	TO	23+215.7	LT		8.09		
23+214.2	TO	23+215.8	RT		8.54		
23+880.3	TO	23+885.6	RT		18.35		
IL RTE 126							
50+020.8	TO	50+030.0	RT	17.21			
US RTE 34							
189+642.4	TO	189+647.0	LT	10.06			
189+649.3	TO	189+659.5	RT	25.44			
189+676.6	TO	189+682.2	RT	15.01			0.412
189+679.4	TO	189+885.0	RT		325.93		0.603
189+681.6	TO	189+685.8	LT		5.19		0.067
189+807.3	TO	189+822.1	LT		26.29		
189+833.3	TO	189+856.4	LT		43.44		0.84
189+866.6	TO	189+879.1	LT		20.15		0.204
189+891.6	TO	189+912.9	LT		39.37		0.726
189+897.8	TO	189+974.3	RT		115.98		
189+918.1	TO	189+941.9	LT		47.00		0.656

CONTINUED ON NEXT SHEET

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES
DATE		DRAWN BY
		CHECKED BY

FILE: 078eah-proop.dgn
PLOTTED: 8/22/2011

HMG JOB NO. 5122