

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(SCS,13C,108,109R)	KENDALL	931	102
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

TEMPORARY PAVEMENT MARKING SCHEDULE

LOCATION	CHANGEABLE MESSAGE SIGN	PAVEMENT MARKING TAPE, TYPE III									WORKZONE PAVEMENT MARKING REMOVAL	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3
		LETTERS & SYMBOLS	LINE												
			100 MM	150 MM	200 MM		300 MM	600MM							
STATION TO STATION	CAL MO	(WHITE) SQ M	SOLID (WHITE) METER	SOLID (YELLOW) METER	SKIP DASH (WHITE) METER	DOTTED (WHITE) METER	SOLID (WHITE) METER	DIAGONAL (YELLOW) METER	SOLID (WHITE) METER	SQ M	METER	METER	EACH	EACH	
STAGE 1															
18+384.1 TO 21+903.5	16.0	15.31	7038.8	7038.8			30.0	175.0	90.0	82.5	1470.4	105	105	2	1
50+016.0 TO 50+223.7			415.4	415.4						3.3	85.2				
STAGE 1B															
20+479.4 TO 20+681.0	2.0		403.2	403.2				100.0	30.0	6.6	113.6				
21+582.2 TO 21+777.5			195.3	390.6							58.6				
STAGE 2A															
21+582.2 TO 21+777.5	2.0		195.3	390.6						6.6	62.5				
STAGE 2															
18+384.1 TO 22+620.0	16.0	23.27	4235.9	8471.8		60.0	225.0	150.0		89.1	1842.3				
50+016.0 TO 50+223.7				207.7						3.3	100.2				
STAGE 3A															
20+484.0 TO 20+660.0			176.0	352.0						6.6	56.8				
STAGE 3B															
20+484.0 TO 20+660.0	2.0	2.94	176.0	352.0			50.0			13.2	70.7				
STAGE 3															
18+384.1 TO 19+515.0	16.0	5.88	200.0	2261.8				100.0		19.8	1449.5				
19+515.0 TO 22+620.0		17.39	3105.0	6210.0		20.0	125.0	150.0		59.4					
50+016.0 TO 50+223.7			207.7	415.4				15.0		3.3	22.7				
STAGE 3C															
20+484.0 TO 20+660.0	2.0		35.0												
STAGE 4															
18+384.1 TO 19+474.0	8.0	55		2704.0	462.0	178.0	525.0	96.0		68.0	1058.5				
19+474.0 TO 22+621.1		23.27		6294.2		10.0	200.0			72.6					
50+016.0 TO 50+223.7				415.4						3.3	68.8				
STAGE 5															
19+474.0 TO 22+416.3	12.0	148		7245.0	1420.0	154.0	780.0	175.0		313.0	738.3	195		4	
22+416.3 TO 23+481.5		17.64	2130.4	2130.4	12.5		386.0	75.0		52.8	584.4				
189+535.5 TO 190+260.0		5.88	1449.0	1449.0			119.0	40.0		13.2	375.2				
1+000.4 TO 1+193.6			193.2	386.4						3.3					
1+000.0 TO 1+142.7			142.7	142.7							28.5				
STAGE 6															
22+416.3 TO 23+869.2	12.0	11.76	2905.8	2905.8				386.0	75.0	49.5	577.0	339	195		3
189+532.9 TO 190+403.3		5.88	1740.8	1740.8				119.0	45.0	16.5	368.1				
1+000.4 TO 1+193.6			193.2	386.4				107.0		3.3	59.9				
1+000.0 TO 1+126.7		2.94	155.2	253.4	92.7					6.6	146.6				
STAGE 7															
22+416.3 TO 23+867.3	12.0	17.64	2902.0	2902.0				352.0	90.0	39.6	722.3		73		2
189+532.9 TO 190+403.3		5.88	1740.8	1740.8				171.0	15.0	19.8	401.2				
1+099.0 TO 1+193.6		2.94		189.2				36.5		6.6	81.3				
1+000.0 TO 1+204.1			244.1	408.2						3.3	47.8				

CONTINUED ON NEXT SHEET

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">SCHEDULE OF QUANTITIES</p> <p align="right">DRAWN BY _____ CHECKED BY _____</p>

FILE: 078sch-pr-opc.dgn
PLOTTED: 8/14/2001

HMG JOB NO. 5122