

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(SCS,13C,108,109R)	KENDALL	931	110
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SANITARY SEWER SCHEDULE

ID	STATION	OFFSET	RT/LT	TO	ID	STATION	OFFSET	RT/LT	SANITARY MANHOLE, TYPE A	SANITARY DROP MANHOLE, TYPE A	SANITARY SEWER REPAIR, 200mm, PVC-DR18	SANITARY SEWER, 150mm, PVC-DR18	SANITARY SEWER, 200mm, PVC-DR18	SANITARY SEWER, 250mm, PVC-DR18	SANITARY SEWER, 200mm, PVC-SDR21	SANITARY SEWER, 250mm, PVC-SDR21	SANITARY SEWER, 300mm, PVC-SDR21	SANITARY SEWER, 150mm, PVC-SDR26	SANITARY SEWER, 200mm, PVC-SDR26	TRENCH BACKFILL	SANITARY MANHOLE TO BE ADJUSTED		FRAMES AND LIDS, SPECIAL		
																					STATE	CITY	STATE	CITY	
MH #21	21+678.5	32.7	LT						1																
MH #23	21+687.3	27.3	RT	TO	MH #22	21+677.2	30.9	LT								58.4				143.2					
MH #24	21+689.1	28.6	RT	TO	MH #23	21+687.3	27.3	RT								1.6				8.3					
MH #25	21+811.1	21.4	RT						1																
S #17	21+811.1	21.4	RT	TO		21+806.6	21.5	RT										4.0		4.0					
S #18	21+811.1	21.4	RT	TO		21+820.1	21.1	RT										9.0		9.0					
	21+947.7	24.4	LT																		1			1	
	22+207.7	13.2	RT																			1			
MH #26	22+215.6	17.8	RT						1						31.3					32.2					
	22+945.7	25.2	RT																		1				
	23+203.6	23.1	RT																		1		1		
	23+226.6	22.6	RT																			1			
US RTE 34																									
	189+699.	18.2	LT																			1			
	189+749.	18.4	LT	TO		189+756.	18.4	LT			7.2										15.2				
	189+813.2	18.7	LT																			1			
	189+820.	13.4	LT																				1		1
	189+892.1	13.0	LT																				1		1
TOTALS									25	1	9.2	76.4	141.8	10.2	97.6	61.6	45.5	43.5	298.2	1977.8	14	7	3	3	
USE									25	1	9.5	76.5	142	10.5	98	62	45.5	43.5	298.5	1,978	14	7	3	3	

FILE: 078sch_prop.dgn
PLOTTED: 8/14/2011

HMG JOB NO. 5122

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES
		DRAWN BY
		CHECKED BY
		DATE