| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 326 | (5CS,13C,108,109)R | KENDALL | 931 | 124 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS | FED. AID PROJECT | |

# STORM SEWER SCHEDULE

| UPSTREAM STRUCTURE | | | | DOWNSTREAM STRUCTURE | | | | TRENCH BACKFILL | STORM SEWERS, RUBBER GASKET | | | | | | | | | | | | | | | | | | | | | STORM SEWER (WATER MAIN REQ.) | STORM SEWERS, CLASS B, TYPE 1 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | CLASS A | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | TYPE 1 | | | | | | | | TYPE 2 | | | | | | | | | | | TYPE 3 | | | | |
| STR # | LOCATION | | | STR # | LOCATION | | | | 300MM | 450MM | 600MM | 750MM | 900MM | 1050MM | 1200MM | 1350MM | 300MM | 450MM | 600MM | 750MM | 900MM | 1050MM | 1200MM | 1350MM | 1500MM | 1650MM | 300MM | 1050MM | 1200MM | 300MM | 1200MM |
| | STATION | OFFSET | | | STATION | OFFSET | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | METER | | | | METER | | CU M | METER | METER | METER | METER | METER | METER | METER | METER | METER | METER | METER | METER | METER | METER | METER | METER | METER | METER | METER | METER | METER | METER | METER |
| 341 | 20+601.500 | 9.335 | RT | 340 | 20+625.400 | 9.485 | RT | 2.431 | 23.264 | | | | | | | | | | | | | | | | | | | | | | |
| 342 | 20+625.400 | 7.700 | LT | 343 | 20+655.000 | 10.235 | LT | 124.651 | | | | | | | | | | | | | | | | | | 28.323 | | | | | |
| 340 | 20+625.400 | 9.485 | RT | 342 | 20+625.400 | 7.700 | LT | 4.463 | 15.573 | | | | | | | | | | | | | | | | | | | | | | |
| 329 | 20+627.000 | 9.485 | LT | 342 | 20+625.399 | 7.700 | LT | 0.429 | | | | | | | | | 0.786 | | | | | | | | | | | | | | |
| 327 | 20+631.986 | 14.089 | LT | 329 | 20+627.000 | 9.485 | LT | 3.203 | | | | | | | | | 5.967 | | | | | | | | | | | | | | |
| 328 | 20+643.642 | 14.239 | LT | 327 | 20+631.986 | 14.089 | LT | 6.149 | | | | | | | | | 11.020 | | | | | | | | | | | | | | |
| 343 | 20+655.000 | 10.235 | LT | 345 | 20+669.000 | 13.925 | LT | 73.933 | | | | | | | | | | | | | | | | | | 13.093 | | | | | |
| 344 | 20+669.000 | 9.485 | LT | 345 | 20+669.000 | 13.925 | LT | 2.105 | 2.828 | | | | | | | | | | | | | | | | | | | | | | |
| 345 | 20+669.000 | 13.925 | LT | 347 | 20+690.000 | 13.925 | LT | 94.520 | | | | | | | | | | | | | | | | | | 19.615 | | | | | |
| 372 | 20+669.000 | 9.335 | RT | 373 | 20+699.000 | 9.485 | RT | 3.817 | 29.364 | | | | | | | | | | | | | | | | | | | | | | |
| 346 | 20+690.000 | 9.485 | LT | 347 | 20+690.000 | 13.925 | LT | 2.105 | 2.828 | | | | | | | | | | | | | | | | | | | | | | |
| 347 | 20+690.000 | 13.925 | LT | 349 | 20+711.000 | 13.925 | LT | 89.095 | | | | | | | | | | | | | | | | | | 19.615 | | | | | |
| 50 | 20+698.513 | 39.662 | LT | 51 | 20+698.531 | 38.154 | LT | 0.133 | 0.706 | | | | | | | | | | | | | | | | | | | | | | |
| 51 | 20+698.531 | 38.154 | LT | 53 | 20+720.531 | 38.619 | LT | 4.047 | 20.855 | | | | | | | | | | | | | | | | | | | | | | |
| 373 | 20+699.000 | 9.485 | RT | 374 | 20+732.000 | 9.485 | RT | 5.919 | 32.181 | | | | | | | | | | | | | | | | | | | | | | |
| 348 | 20+711.000 | 9.485 | LT | 349 | 20+711.000 | 13.925 | LT | 2.105 | 2.828 | | | | | | | | | | | | | | | | | | | | | | |
| 349 | 20+711.000 | 13.925 | LT | 351 | 20+730.000 | 13.925 | LT | 84.480 | | | | | | | | | | | | | | | | | | 17.615 | | | | | |
| 52 | 20+720.514 | 40.127 | LT | 53 | 20+720.531 | 38.619 | LT | 0.131 | 0.706 | | | | | | | | | | | | | | | | | | | | | | |
| 53 | 20+720.531 | 38.619 | LT | 55 | 20+742.531 | 39.085 | LT | 5.783 | 20.855 | | | | | | | | | | | | | | | | | | | | | | |
| 350 | 20+730.000 | 9.485 | LT | 351 | 20+730.000 | 13.925 | LT | 2.105 | 2.828 | | | | | | | | | | | | | | | | | | | | | | |
| 351 | 20+730.000 | 13.925 | LT | 353 | 20+749.000 | 13.775 | LT | 81.935 | | | | | | | | | | | | | | | | | | 17.373 | | | | | |
| 374 | 20+732.000 | 9.485 | RT | 375 | 20+765.000 | 9.485 | RT | 7.284 | 32.181 | | | | | | | | | | | | | | | | | | | | | | |
| 54 | 20+742.514 | 40.592 | LT | 55 | 20+742.531 | 39.085 | LT | 0.129 | 0.705 | | | | | | | | | | | | | | | | | | | | | | |
| 55 | 20+742.531 | 39.085 | LT | 56 | 20+749.000 | 39.221 | LT | 4.406 | | | | | | | | | 5.321 | | | | | | | | | | | | | | |
| 352 | 20+749.000 | 9.485 | LT | 353 | 20+749.000 | 13.775 | LT | 1.872 | 2.524 | | | | | | | | | | | | | | | | | | | | | | |
| 353 | 20+749.000 | 13.775 | LT | 355 | 20+772.000 | 13.775 | LT | 92.698 | | | | | | | | | | | | | | | | | | 21.130 | | | | | |
| 58 | 20+749.000 | 22.000 | LT | 353 | 20+749.000 | 13.775 | LT | | | | | | | | | | 6.294 | | | | | | | | | | | | | | |
| 57 | 20+749.000 | 30.000 | LT | 58 | 20+749.000 | 22.000 | LT | | | | | | | | | | | | | | | | | | | | 6.851 | | | | |
| 56 | 20+749.000 | 39.221 | LT | 57 | 20+749.000 | 30.000 | LT | 6.215 | | | | | | | | | | | | | | | | | | | 8.072 | | | | |
| 49 | 20+756.438 | 48.636 | LT | 56 | 20+749.000 | 39.221 | LT | 8.336 | | | | | | | | | 11.014 | | | | | | | | | | | | | | |
| 48 | 20+756.598 | 53.607 | LT | 49 | 20+756.438 | 48.636 | LT | 0.454 | 4.337 | | | | | | | | | | | | | | | | | | | | | | |
| 375 | 20+765.000 | 9.485 | RT | 376 | 20+792.000 | 9.485 | RT | 5.813 | 26.181 | | | | | | | | | | | | | | | | | | | | | | |
| 354 | 20+772.000 | 9.485 | LT | 355 | 20+772.000 | 13.775 | LT | 1.872 | 2.524 | | | | | | | | | | | | | | | | | | | | | | |
| 355 | 20+772.000 | 13.775 | LT | 357 | 20+795.000 | 13.775 | LT | 85.894 | | | | | | | | | | | | | | | | | | 21.130 | | | | | |
| 376 | 20+792.000 | 9.485 | RT | 377 | 20+819.000 | 9.485 | RT | 11.816 | | | | | | | | | 26.181 | | | | | | | | | | | | | | |
| 356 | 20+795.000 | 9.485 | LT | 357 | 20+795.000 | 13.775 | LT | 1.872 | 2.524 | | | | | | | | | | | | | | | | | | | | | | |
| 357 | 20+795.000 | 13.775 | LT | 360 | 20+808.000 | 6.100 | LT | 59.179 | | | | | | | | | | | | | | | | | | 13.226 | | | | | |
| 360 | 20+808.000 | 6.100 | LT | 361 | 20+827.000 | 5.150 | RT | 112.988 | | | | | | | | | | | | | | | | | | 21.918 | | | | | |
| 359 | 20+815.000 | 9.485 | LT | 360 | 20+808.000 | 6.100 | LT | 5.806 | | | | | | | | | 8.115 | | | | | | | | | | | | | | |
| 358 | 20+818.406 | 14.825 | LT | 359 | 20+815.000 | 9.485 | LT | 2.612 | 5.515 | | | | | | | | | | | | | | | | | | | | | | |
| 377 | 20+819.000 | 9.485 | RT | 361 | 20+827.000 | 5.150 | RT | 6.426 | | | | | | | | | 7.553 | | | | | | | | | | | | | | |
| 361 | 20+827.000 | 5.150 | RT | 381 | 20+842.700 | 5.150 | RT | 161.946 | | | | | | | | | | | | | | | 28.798 | | | | | | | | |
| 380 | 20+834.200 | 9.500 | RT | 371 | 20+843.000 | 9.485 | RT | 3.917 | | | | | | | | | 7.981 | | | | | | | | | | | | | | |

CONTINUED

| REVISIONS | |
|---|---|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

STORM SEWER SCHEDULE

DRAWN BY

DATE CHECKED BY

HMG JOB NO. 5122

FILE: 119sch_ss.dgn
PLOTTED: 8/14/2011