

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(SCS,13C,108,109)R	KENDALL	931	125
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STORM SEWER SCHEDULE

STR #	UPSTREAM STRUCTURE		STR #	DOWNSTREAM STRUCTURE		TRENCH BACKFILL	STORM SEWERS, RUBBER GASKET																				STORM SEWER (WATER MAIN REQ.)	STORM SEWERS, CLASS B, TYPE 1			
	LOCATION			LOCATION			CLASS A										TYPE 2						TYPE 3								
	STATION	OFFSET		STATION	OFFSET		300MM	450MM	600MM	750MM	900MM	1050MM	1200MM	1350MM	300MM	450MM	600MM	750MM	900MM	1050MM	1200MM	1350MM	1500MM	1650MM	300MM	1050MM			1200MM	300MM	1200MM
	METER			METER			CU M	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER	METER			METER	METER	METER
378	20+835.669	17.749	RT	379	20+835.700	15.045	RT	0.257	2.067																						
379	20+835.700	15.045	RT	380	20+834.200	9.500	RT	1.054	4.925																						
362	20+842.700	9.683	LT	381	20+842.700	5.387	RT	11.586																							
381	20+842.700	5.150	RT	384	20+884.000	5.150	RT	343.286																							
371	20+843.000	9.485	RT	381	20+842.700	5.387	RT	1.421																							
65	20+863.500	9.336	LT	64	20+884.000	9.186	LT	2.718	19.864																						
382	20+863.500	9.335	RT	383	20+883.700	9.185	RT	2.669	19.564																						
383	20+883.700	9.185	RT	384	20+884.000	5.149	RT	1.142																							
64	20+884.000	9.186	LT	384	20+884.000	5.149	RT	9.593																							
384	20+884.000	5.150	RT	389	20+921.300	5.300	RT	270.454																							
385	20+904.500	9.335	RT	387	20+921.000	9.185	RT	1.933	15.864																						
392	20+906.000	9.336	LT	390	20+921.000	9.186	LT	1.818	14.364																						
390	20+921.000	9.186	LT	389	20+921.300	5.300	RT	7.807																							
387	20+921.000	9.185	RT	389	20+921.300	5.300	RT	0.814																							
389	20+921.300	5.300	RT	398	20+959.465	21.873	RT	94.743																							
391	20+922.600	9.336	LT	390	20+921.000	9.186	LT	0.123	0.970																						
386	20+923.755	9.335	RT	387	20+921.000	9.185	RT	0.259	2.122																						
397	20+943.769	23.039	RT	398	20+959.464	21.872	RT	12.955																							
394	20+951.182	10.112	RT	395	20+956.798	9.187	RT	0.789	5.055																						
395	20+956.798	9.187	RT	396	20+958.155	14.000	RT	1.915	4.182																						
396	20+958.155	14.000	RT	398	20+959.464	21.872	RT	4.726																							
398	20+959.465	21.873	RT	399	21+005.710	19.921	RT	311.190																							
420	20+940.928	19.906	LT	419	20+942.500	9.701	LT	2.210	9.689																						
419	20+942.500	9.701	LT	418	20+950.800	9.178	LT	2.476	7.497																						
418	20+950.800	9.178	LT	417	20+953.800	9.134	LT	0.682	2.181																						
417	20+953.800	9.134	LT	416	20+956.891	10.526	LT	2.036																							
FOX RIVER																															
666	21+207.834	8.665	LT	EX	21+208.979	14.761	LT																								
667	21+210.847	8.815	LT	EX	21+208.979	14.761	LT																								
668	21+230.019	8.817	LT	667	21+210.847	8.815	LT	3.128	18.353																						
669	21+242.497	16.027	LT	668	21+230.019	8.817	LT	7.407	13.775																						
664	21+192.831	16.751	RT	665	21+182.606	18.593	RT																								
663	21+200.420	15.415	RT	664	21+192.831	16.751	RT																								
660	21+207.500	14.200	RT	663	21+200.420	15.415	RT																								
661	21+207.511	8.940	RT	660	21+207.500	14.200	RT	1.903																							
662	21+210.507	8.856	RT	661	21+207.511	8.940	RT	0.320	2.360																						
659	21+216.000	13.800	RT	660	21+207.500	14.200	RT																								
658	21+225.000	13.500	RT	659	21+216.000	13.800	RT	39.367																							
657	21+238.000	13.200	RT	658	21+225.000	13.500	RT	20.752																							

CONTINUED

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		STORM SEWER SCHEDULE
		DRAWN BY
		CHECKED BY
		DATE

FILE: 119sch_ss.dgn
PLOTTED: 8/14/2011

HMG JOB NO. 5122