F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(5CS,13C,108,109)R	KENDALL	931	145
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

STORM SEWER SCHEDULE

UPSTREAM STRUCTURE				DOWNSTREAM STRUCTURE				MANHOLES, TYPE A																					INLETS										
								1.2 M DIAMETER						1.5 M DIAMETER					1.8 M DIAMETER			2.1 M DIAMETER		2.4 M DIAMETER					2.7 M DIAMETER		TYPE A				TYPE B						
STR #	LOCATION			STR #	LOCATION			TYPE 1 FRAME, CLOSED LID	TYPE 3V F&G	TYPE 5 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 11V F&G	TYPE 20 F&G	TYPE 1 FRAME, CLOSED LID	TYPE 3V F&G	TYPE 5 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 11V F&G	TYPE 1 FRAME, CLOSED LID	TYPE 5 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 1 FRAME, CLOSED LID	TYPE 3V F&G	TYPE 1 FRAME, CLOSED LID	TYPE 5 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 11V F&G	SPECIAL	TYPE 5 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 3V F&G	TYPE 8 GRATE	TYPE 11V F&G	TYPE 20 F&G	TYPE 1 FRAME, CLOSED LID	TYPE 1 FRAME, OPEN LID	TYPE 3V F&G	TYPE 5 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 11V F&G	TYPE 20 F&G
	STATION	OFFSET			STATION	OFFSET																																		
		METER				METER		EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
680	21+586.541	17.240	RT	618	21+594.887	16.979	RT																														1			
678	21+589.060	16.981	LT	679	21+595.036	19.000	LT																							1										
619	21+594.500	13.200	RT	622	21+568.000	13.200	RT													1																				
618	21+594.887	16.979	RT	619	21+594.500	13.200	RT			1																														
617	21+601.383	17.022	RT	618	21+594.887	16.979	RT																							1										
677	21+604.405	17.110	LT	679	21+595.036	19.000	LT																														1			
679	21+595.036	19.000	LT							1																														
676	21+618.500	10.217	LT	677	21+604.405	17.110	LT																														1			
615	21+618.500	13.200	RT	619	21+594.500	13.200	RT												1																					
614	21+618.500	10.217	RT	615	21+618.500	13.200	RT																														1			
675	21+621.500	10.068	LT	676	21+618.500	10.217	LT																							1										
613	21+621.500	10.067	RT	614	21+618.500	10.217	RT																							1										
610	21+656.000	10.217	LT	611	21+656.000	10.217	RT																														1			
612	21+656.000	13.200	RT	615	21+618.500	13.200	RT												1																					
611	21+656.000	10.217	RT	612	21+656.000	13.200	RT																														1			
609	21+671.668	19.962	LT	610	21+656.000	10.217	LT																														1			
604	21+676.954	16.400	RT	605	21+677.995	19.228	RT																							1										
605	21+677.995	19.228	RT	606	21+680.000	19.228	RT																														1			
606	21+680.000	19.228	RT	607	21+680.000	13.200	RT			1																														
607	21+680.000	13.200	RT	612	21+656.000	13.200	RT													1																				
608	21+685.293	22.554	LT	609	21+671.668	19.962	LT																							1										
593	21+721.250	19.129	LT																												1									
599	21+724.737	10.068	LT	600	21+727.737	10.218	LT																							1										
601	21+724.737	10.066	RT	602	21+727.737	10.216	RT																							1										
600	21+727.737	10.218	LT	602	21+727.737	10.216	RT																														1			
602	21+727.737	10.216	RT	603	21+729.400	13.200	RT																														1			
603	21+729.400	13.200	RT	607	21+680.000	13.200	RT												1																					
598	21+731.770	17.374	RT	603	21+729.400	13.200	RT																											1						
594	21+751.000	10.067	LT	595	21+751.000	10.217	RT																							1										
596	21+751.000	18.297	RT	597	21+751.000	13.200	RT																																	
597	21+751.000	13.200	RT	603	21+729.400	13.200	RT												1																					
595	21+751.000	10.217	RT	597	21+751.000	13.200	RT																														1			
590	21+790.000	10.067	LT	591	21+790.000	10.217	RT																							1										
592	21+790.000	13.200	RT	597	21+751.000	13.200	RT												1																					
591	21+790.000	10.217	RT	592	21+790.000	13.200	RT																														1			
587	21+831.000	10.700	LT	588	21+831.000	10.700	RT																				1													
588	21+831.000	10.700	RT	592	21+790.000	13.200	RT																				1													
586	21+858.000	12.000	LT	587	21+831.000	10.700	LT												1																					
589	21+858.019	10.067	LT	586	21+858.000	12.000	LT																							1										
585	21+872.500	12.000	LT	586	21+858.000	12.000	LT												1																					
584	21+872.500	16.000	LT	585	21+872.500	12.000	LT																								1									
581	21+875.000	16.374	RT	582	21+875.000	10.367	RT																								1									
582	21+875.000	10.367	RT	588	21+831.000	10.700	RT		1																															

CONTINUED

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STORM SEWER SCHEDULE

DRAWN BY

DATE CHECKED BY

HMG JOB NO. 5122

FILE: 119sch_ss.dgn
PLOTTED: 8/14/2011