CONTRACT NO. 66671

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(5CS,13C,108,109)R	KENDALL	931	152
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STORM SEWER SCHEDULE

UPSTREAM STRUCTURE				DOWNSTREAM STRUCTURE				MANHOLES, TYPE A																				INLETS										
								1.2 M DIAMETER						1.5 M DIAMETER					1.8 M DIAMETER			2.1 M DIAMETER		2.4 M DIAMETER					2.7 M DIAMETER		TYPE A				TYPE B						
STR #	LOCATION			STR #	LOCATION			TYPE 1 FRAME, CLOSED LID	TYPE 3V F&G	TYPE 5 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 11V F&G	TYPE 20 F&G	TYPE 1 FRAME, CLOSED LID	TYPE 3V F&G	TYPE 5 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 11V F&G	TYPE 1 FRAME, CLOSED LID	TYPE 5 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 1 FRAME, CLOSED LID	TYPE 3V F&G	TYPE 1 FRAME, CLOSED LID	TYPE 5 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 11V F&G	SPECIAL	TYPE 5 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 3V F&G	TYPE 8 GRATE	TYPE 11V F&G	TYPE 20 F&G	TYPE 1 FRAME, CLOSED LID	TYPE 1 FRAME, OPEN LID	TYPE 3V F&G	TYPE 5 FRAME, CLOSED LID	TYPE 8 GRATE	TYPE 11V F&G	TYPE 20 F&G
	STATION	OFFSET METER			STATION	OFFSET METER		EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
784	189+850.000	4.439 LT		785	189+845.000	4.406 LT																										1						
779	189+894.355	24.758 LT		780	189+905.000	15.716 LT		1																														
780	189+905.000	15.716 LT		787	189+844.979	15.293 LT								1																								
778	189+905.000	5.516 LT		780	189+905.000	15.716 LT																													1			
777	189+905.000	13.968 RT		778	189+905.000	5.516 LT																									1							
726	189+935.000	13.968 RT		727	189+943.750	14.418 RT																									1							
728	189+940.749	5.366 LT		729	189+943.749	5.666 LT																									1							
775	189+943.750	16.998 LT		776	189+943.750	15.000 LT																													1			
776	189+943.750	15.000 LT		780	189+905.000	15.716 LT									1																							
729	189+943.750	5.666 LT		776	189+943.750	15.000 LT			1																													
727	189+943.750	14.418 RT		729	189+943.750	5.666 LT								1																								
774	189+947.287	17.187 LT		775	189+943.750	16.998 LT																									1							
725	189+963.050	22.568 RT		727	189+943.750	14.418 RT											1																					
724	189+967.003	14.752 RT		725	189+963.050	22.568 RT																									1							
773	189+972.500	15.000 LT		776	189+943.750	15.000 LT														1																		
723	189+974.891	37.443 RT		725	189+963.050	22.568 RT											1																					
766	190+021.696	23.815 RT		767	190+034.786	14.971 RT																									1							
840	190+025.995	20.866 LT		772	190+026.000	15.000 LT																									1							
772	190+026.000	15.000 LT		773	189+972.500	15.000 LT									1																							
767	190+034.786	14.971 RT		768	190+048.000	13.455 RT																													1			
764	190+045.000	18.066 LT		763	190+046.500	18.216 LT																									1							
770	190+046.293	1.268 RT		769	190+048.000	1.568 RT																									1							
82	190+046.370	19.875 LT		763	190+046.500	18.216 LT																													1			
763	190+046.500	18.216 LT		771	190+048.000	15.799 LT																																
771	190+048.000	15.800 LT		772	190+026.000	15.000 LT									1																							
768	190+048.000	13.455 RT		769	190+048.000	1.568 RT			1																													
769	190+048.000	1.568 RT		771	190+048.000	15.800 LT			1																													
765	190+054.100	12.559 RT		768	190+048.000	13.455 RT																									1							
754	190+084.000	18.066 LT		755	190+084.000	15.800 LT																									1							
755	190+084.000	15.800 LT		771	190+048.000	15.800 LT				1																												
761	190+084.000	11.168 RT		762	190+084.000	1.268 RT																									1							
762	190+084.000	1.268 RT		755	190+084.000	15.800 LT																													1			
751	190+109.000	21.238 LT		752	190+109.000	18.216 LT																										1						
752	190+109.000	18.216 LT		753	190+109.000	15.800 LT																													1			
753	190+109.000	15.800 LT		755	190+084.000	15.800 LT				1																												
757	190+132.000	16.200 RT		759	190+133.000	11.466 RT																											1					
756	190+133.000	18.066 LT		750	190+133.000	15.800 LT																									1							
750	190+133.000	15.800 LT		753	190+109.000	15.800 LT				1																												
759	190+133.000	11.466 RT		760	190+133.000	1.418 RT			1																													
760	190+133.000	1.418 RT		750	190+133.000	15.800 LT																													1			
758	190+138.000	14.333 RT		759	190+133.000	11.466 RT																											1					
81	190+172.345	21.238 LT		748	190+176.750	21.249 LT																												1				
748	190+176.750	21.249 LT		749	190+176.750	16.500 LT																																1

CONTINUED

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STORM SEWER SCHEDULE

DRAWN BY

DATE CHECKED BY

HMG JOB NO. 5122

FILE: 119sch_ss.dgn
PLOTTED: 8/14/2011

HMG ENGINEERS, INC., 1075 LAKE RD., P.O. BOX 70, CARLYLE, ILLINOIS 62231 (618)-594-3711 WWW.HMGENGINEERS.COM