

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QTY	CONSTRUCTION TYPE CODE				
				RURAL RDWY 0004	URBAN RDWY 0004	006-0020 006-0021 RURAL 0011	006-0131 RURAL 0014	006-0176 006-0177 RURAL 0013
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	541	541				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	204	204				
20101000	TEMPORARY FENCE	FOOT	500	500				
20200100	EARTH EXCAVATION	CU YD	1769	1769				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	12720	12720				
20400800	FURNISHED EXCAVATION	CU YD	50500	50500				
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	32343	32343				
25000300	SEEDING, CLASS 3	ACRE	16.25	16.25				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1373	1373				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1373	1373				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1373	1373				
25100115	MULCH METHOD 2	ACRE	16.25	16.25				
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	73784	73784				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1525	1525				
28000305	TEMPORARY DITCH CHECKS	FOOT	2333	2333				
28000400	PERIMETER EROSION BARRIER	FOOT	18277	18277				
28000500	INLET AND PIPE PROTECTION	EACH	8	8				
28100107	STONE RIPRAP, CLASS A4	SQ YD	33	33				
28200200	FILTER FABRIC	SQ YD	33	33				
31100500	SUBBASE GRANULAR MATERIAL, TYPE A 6"	SQ YD	521	521				
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	453	453				
31102100	SUB-BASE GRANULAR MATERIAL, TYPE C 4"	SQ YD	12578	12578				
31200100	STABILIZED SUBBASE 4"	SQ YD	17531	17531				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	34339	17838	16501			
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2831	2831.0				
40600300	AGGREGATE (PRIME COAT)	TON	484	269	215			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	43	23	20			
40600745	POLYMERIZED LEVELING BINDER (HAND METHOD), N90	TON	87	44	43			
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	TON	502	502				
40600895	CONSTRUCTING TEST STRIP	EACH	14	14				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2992	1496	1496			
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	3400	1700	1700			
40600990	TEMPORARY RAMP	SQ YD	192	96	96			
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1132	1132				
40603243	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90	TON	25297	15162	10135			

* SPECIALTY ITEMS

FILE NAME =	USER NAME = braboygo	DESIGNED -	REVISED -
of:\pwork\pwork\braboygo\d8212731\0368686-shr-cover.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	[106-5]HBR-1,VBR(06-6)RS-3&I	BUREAU	249	3
CONTRACT NO. 66686			ILLINOIS FED. AID PROJECT	