

GIRDER 12 - EASTBOUND

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. W. Abut.	3078+53.10	22.10	754.78	754.78
@ Brg. W. Abut.	3078+54.52	22.06	754.80	754.80
A	3078+64.41	21.81	754.96	754.97
B	3078+74.30	21.58	755.12	755.14
C	3078+84.18	21.37	755.27	755.30
D	3078+94.07	21.18	755.43	755.45
E	3079+03.95	21.00	755.58	755.59
F	3079+13.84	20.84	755.73	755.72
G	3079+23.73	20.69	755.88	755.87
@ Brg. Pier 1	3079+31.64	20.59	756.00	756.00
H	3079+41.53	20.48	756.14	756.18
I	3079+51.42	20.38	756.28	756.37
J	3079+61.30	20.31	756.42	756.56
K	3079+71.19	20.25	756.56	756.74
L	3079+81.08	20.20	756.70	756.90
M	3079+90.97	20.18	756.83	757.05
N	3080+00.86	20.17	756.97	757.17
O	3080+10.75	20.18	757.10	757.26
P	3080+20.64	20.20	757.23	757.34
Q	3080+30.53	20.24	757.35	757.42
R	3080+40.42	20.30	757.48	757.50
@ Brg. Pier 2	3080+47.34	20.36	757.57	757.57
S	3080+57.23	20.45	757.69	757.68
T	3080+67.12	20.55	757.81	757.81
U	3080+77.00	20.68	757.93	757.94
V	3080+86.89	20.82	758.04	758.06
W	3080+96.78	20.98	758.16	758.18
X	3081+06.66	21.15	758.27	758.29
Y	3081+16.55	21.34	758.38	758.39
@ Brg. E. Abut.	3081+24.45	21.51	758.46	758.46
Bk. E. Abut.	3081+25.88	21.54	758.48	758.48

FILE NAME =	USER NAME =	DESIGNED - DY	REVISED -
TYLIN INTERNATIONAL		CHECKED - PF	REVISED -
PLOT SCALE =		DRAWN - DY	REVISED -
PLOT DATE = 09/13/2011		CHECKED - PF	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**TOP OF SLAB ELEVATIONS - EASTBOUND (2 of 2)
STRUCTURE NO. 006-0176 EB AND 006-0177 WB**

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	[(06-5)HBR-1.VBR(06-6)RS-3&1	BUREAU	241	11
			CONTRACT NO. 66686	
ILLINOIS FED. AID PROJECT				