

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	0011 HENDERSON				100% STATE
				DIXON	WOLF	DIXON	WOLF	0004
				IL RTE 94	IL RTE 94/116	IL RTE 94	IL RTE 94/116	IL RTE 94/116
				STR. NO. 036-0054	STR. NO. 036-0055	0004 ROADWAY	0004 ROADWAY	MOWING
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1437			861	576	
40600990	TEMPORARY RAMP	SQ YD	42			42		
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1301			726	575	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1284			1097	187	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	37			37		
2 42001165	BRIDGE APPROACH PAVEMENT	SQ YD	444			222	222	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	86			43	43	
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	8475			8475		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1720			1720		
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	50			25	25	
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	50			25	25	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	390			325	65	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	458			271	187	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1			
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1				
50105220	PIPE CULVERT REMOVAL	FOOT	100			82	18	
50200100	STRUCTURE EXCAVATION	CU YD	292	138	154			
50300225	CONCRETE STRUCTURES	CU YD	100.7	50.9	49.8			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	362.4	182.5	179.9			
50300260	BRIDGE DECK GROOVING	SQ YD	448	224	224			
50300100	FLOOR DRAINS	EACH	8	8				
50300300	PROTECTIVE COAT	SQ YD	1132	566	566			
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	0.5	0.5			
50500505	STUD SHEAR CONNECTORS	EACH	1800	900	900			

2 REVISED
11/9/2011

FILE NAME =
c:\pwork\pwork\johnson\td0248162\0460083-sht-plen.dgn

USER NAME = johnson
PLOT SCALE = 100.0000' / 1" =
PLOT DATE = 8/26/2011

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

NOT TO SCALE SHEET NO. 2 OF 5 SHEETS STA. TO STA.

F.A.P. RTE. 534	SECTION 109B (BR-2), 109B (BR-3)	COUNTY HENDERSON	TOTAL SHEETS 88	SHEET NO. 6
CONTRACT NO. 68083				
ILLINOIS FED. AID PROJECT				