

EARTHWORK							
LOCATION	EARTH EXCAVATION	EARTH EX. ADJUST FOR SHRINKAGE	EMBANKMENT	(-) FURNISHED EX. / (+) WASTE	CHANNEL EXCAVATION	CHANNEL EX. ADJUST FOR SHRINKAGE	TOPSOIL EXCAVATION & PLACEMENT
	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
WOLF CREEK							
STA. 212+10 TO 213+00	2.96	2.22	61.67	-59.45			97
STA. 213+00 TO 214+00	58.33	43.75	237.04	-193.29			110
STA. 214+00 TO 215+00	83.33	62.50	398.15	-335.65			110
STA. 215+00 TO 216+26.75	164.82	123.62	676.00	-127.08	567	425.3	113.5
STA. 216+63.25 TO 217+00	268.34	201.26	70.78	+554.98	566	424.5	14.6
STA. 217+00 TO 218+00	1059.33	794.50	100.00	+694.50			110
STA. 218+00 TO 219+00	1924.07	693.05	9.26	+683.79			110
STA. 219+00 TO 219+40	417.04	312.78	2.22	+310.56			43
WOLF CREEK - TOTAL	3978.2	2233.7	1555.1	+1528.4	1133	849.8	708.1
DIXON CREEK							
STA. 342+00 TO 342+15	30.00	22.50	0.28	+22.22			16
STA. 342+15 TO 343+00	248.70	186.53	4.72	+181.81			94
STA. 343+00 TO 344+00	187.04	140.28	29.63	+110.65			111
STA. 344+00 TO 345+00	135.19	101.39	144.44	-43.05			111
STA. 345+00 TO 346+00	66.67	50.00	272.22	-222.22			111
STA. 346+00 TO 346+94.50	77.00	57.75	580.03	-109.78	550	412.50	105
STA. 347+77.50 TO 349+00	224.58	168.44	151.15	+429.04	549	411.75	137.1
STA. 349+00 TO 350+00	222.22	166.67	51.85	+114.82			111
STA. 350+00 TO 350+68	109.56	82.17	32.74	+49.43			75.5
STA. 350+68 TO 351+15	28.72	21.54	11.31	+10.23			52.1
DIXON CREEK - TOTAL	1329.7	997.3	1278.4	+543.2	1099	824.3	923.7
SUB-TOTAL	5307.9	3231.0	2833.5	2071.5	2232.0	1674.1	1631.8
TOTAL	5,310			+2075	2,235		1,635

EPOXY PAVEMENT MARKING - LINE 4"			
LOCATION	WHITE SOLID	YELLOW SOLID	YELLOW SKIP DASH
	FOOT	FOOT	FOOT
WOLF CREEK - IL RTE. 94/116			
STA. 212+10 TO 219+40	1460		190
STA. 212+10 TO 213+75		165	
WOLF CREEK - TOTAL	1460	165	190
DIXON CREEK - IL RTE. 94			
STA. 307+06.65 TO 321+00	2787	2787	
STA. 321+00 TO 332+00	2200	1100	275
STA. 332+00 TO 342+00	2000	1000	250
STA. 342+00 TO 342+15	30	30	
STA. 342+15 TO 351+15	1800		230
STA. 342+15 TO 342+50		35	
DIXON CREEK - TOTAL	8817	4952	755
SUB-TOTAL	10,277	5,117	945
TOTAL	16,339		

AGGREGATE SURFACE COURSE, TYPE B	
LOCATION	TON
STA. 214+62 - ENTRANCE	106.4
WOLF CREEK - TOTAL	106.4
STA. 344+30 - ENTRANCE	81.9
STA. 351+00 - ENTRANCE	61.1
DIXON CREEK - TOTAL	143
TOTAL	249

LOCATION	MULCH METHOD 2	SEEDING, CL 2	SEEDING, CL 3	TEMPORARY EROSION CONTROL SEEDING	FERTILIZER*		
	ACRE	ACRE	ACRE	POUND	NITROGEN POUND	PHOSPHORUS POUND	POTASSIUM POUND
WOLF CREEK							
STA. 212+10 TO 216+13.495 LT & RT	1.25	0.50	1.00	450	120	120	120
STA. 216+76.505 TO 219+40 LT & RT							
WOLF CREEK - TOTAL	1.25	0.50	1.00	450	120	120	120
DIXON CREEK							
STA. 342+15 TO 347+04.50 LT & RT	1.50	0.50	1.50	525	157	157	157
STA. 347+67.50 TO 351+15 LT & RT							
DIXON CREEK - TOTAL	1.50	0.50	1.50	525	157	157	157
TOTAL	2.75	1.00	2.50	975	277	277	277

*FERTILIZER APPLICATION RATE 90 LB/ACRE

BRIDGE APPROACH PAVEMENT	
LOCATION	SQ YD
STA. 216+13.50 TO 216+76.50	222.2
WOLF CREEK - TOTAL	222.2
STA. 347+05.75 TO 347+67.50	222.2
DIXON CREEK - TOTAL	222.2
TOTAL	444

PERIMETER EROSION BARRIER	
LOCATION	FOOT
WOLF CREEK	3560
DIXON CREEK	3672
TOTAL	7,232

TEMPORARY PAVEMENT MARKING				
LOCATION	4"			**24"
	COLOR	CONDITIONS	FOOT	FOOT
WOLF CREEK - IL RTE. 94/116				
*STA. 213+23.50 TO 219+66.50 PHASE I	WHITE	EAST & WEST EDGE	1286	24
*STA. 213+23.50 TO 219+66.50 PHASE II	WHITE	EAST & WEST EDGE	1286	24
WOLF CREEK - TOTAL			2572	48
DIXON CREEK - IL RTE. 94				
*STA. 344+14.50 TO 350+57.50 PHASE I	WHITE	EAST & WEST EDGE	1286	24
*STA. 344+14.50 TO 350+57.50 PHASE II	WHITE	EAST & WEST EDGE	1286	24
DIXON CREEK - TOTAL			2572	48
TOTAL			5,144	96

*STOP BAR TO STOP BAR @ STD 701321

** 2 STOP BARS PER PHASE

REVISÉD 11/9/2011

FILE NAME =	USER NAME = johnsonv	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE. 534	SECTION 109B (BR-2), 109B (BR-3)	COUNTY HENDERSON	TOTAL SHEETS 88	SHEET NO. 16
c:\pwork\pwork\johnsonv\10248162\10248163-shit-plan.dgn	8883-shit-plan.dgn	DRAWN -	REVISED -		NOT TO SCALE	SHEET NO. 4 OF 4 SHEETS	STA.	TO STA.	CONTRACT NO. 68083			
PLOT SCALE = 100.0000' / in.		CHECKED -	REVISED -		ILLINOIS FED. AID PROJECT							
PLOT DATE = 8/26/2011		DATE -	REVISED -									