

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	0011 HENDERSON				0004
				DIXON	WOLF	DIXON	WOLF	100% STATE
				IL RTE 94 STR. NO. 036-0054	IL RTE 94/116 STR. NO. 036-0055	IL RTE 94 0004 ROADWAY	IL RTE 94/116 0004 ROADWAY	IL RTE 94/116 MOWING
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12			6	6	
67100100	MOBILIZATION	L SUM	1			0.5	0.5	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2			1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1			0.5	0.5	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1			0.5	0.5	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1			0.5	0.5	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10			5	5	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2			1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1500			1281	219	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5144			2572	2572	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	96			48	48	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1139			645	494	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	955	63	63	492	337	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	955	63	63	492	337	
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	16339			14524	1815	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	19			10	9	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8			4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	42	21	21			
X0324431	TEMPORARY SOIL RETENTION SYSTEM (TO REMAIN IN PLACE)	SQ FT	803	396	407			
X2503100	MOWING	UNIT	49					49
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	427			427		
X6670109	PERMANENT SURVEY TIES	EACH	8			4	4	
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14			7	7	
Z0001002	GUARDRAIL AGGREGATE EROSION CONTROL	TON	107			56	51	

*SPECIALTY
ITEM