

TRAFFIC CONTROL SURVEILLANCE	
LOCATION	CAL DA
STA. 212+10 TO 216+13.495	5
STA. 216+76.505 TO 219+40	
WOLF CREEK - TOTAL	
STA. 342+15 TO 347+04.50	5
STA. 347+67.50 TO 351+15	
DIXON CREEK - TOTAL	
TOTAL	10

LOCATION	PIPE CULVERT REMOVAL		PIPE CULVERTS, CL D, TY 1, 15"		STEEL END SECTIONS 15"
	OFFSET (FT)	FOOT	OFFSET (FT)	FOOT	EACH
RT. - STA. 214+62	31	18	43	48	2
WOLF CREEK - TOTAL		18		48	2
LT. - STA. 344+30	26	38	33	44	2
RT. - STA. 350+20	30	44	30	24	2
DIXON CREEK - TOTAL		82		68	4
TOTAL		100		116	6

GUARDRAIL SCHEDULE							
LOCATION	TRAFFIC BARRIER TERMINAL, TY. 1 (SPL.) TANGENT	TRAFFIC BARRIER TERMINAL, TY. 6 (ATTACHED TO STRUCTURE)	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6' POSTS	GUARDRAIL AGGREGATE EROSION CONTROL	GUARDRAIL REMOVAL	GUARDRAIL MARKERS, TYPE A	TERMINAL MARKER - DIRECT APPLIED
WOLF CREEK - MAIN LINE	EACH	EACH	FOOT	TON	FOOT	EACH	EACH
STA. 214+81.45 TO 215+31.45 LT.	1			5.07			1
STA. 215+31.45 TO 215+81.45 LT.			50	5.07	101		
STA. 215+81.45 TO 216+12.10 LT.		1		1.39			
STA. 216+75.10 TO 217+05.75 LT.		1		1.39			
STA. 217+05.75 TO 218+05.75 LT.			100	10.13	101		
STA. 218+05.75 TO 218+55.75 LT.	1			5.07			1
STA. 214+81.45 TO 218+55.75 LT.						5	
STA. 214+84.25 TO 215+34.25 RT.	1			5.07			1
STA. 215+34.25 TO 215+84.25 RT.			50	5.07	101		
STA. 215+84.25 TO 216+14.90 RT.		1		1.39			
STA. 216+77.90 TO 217+08.55 RT.		1		1.39			
STA. 217+08.55 TO 217+58.55 RT.			50	5.07	101		
STA. 217+58.55 TO 218+08.55 RT.	1			5.07			1
STA. 214+84.25 TO 218+08.55 RT.						4	
WOLF CREEK - TOTAL	4	4	250	51.17	404	9	4
DIXON CREEK - MAIN LINE							
STA. 345+73.85 TO 346+23.85 LT.	1			5.07			1
STA. 346+23.85 TO 346+73.85 LT.			50	5.07	101		
STA. 346+73.85 TO 347+04.50 LT.		1		1.39			
STA. 347+67.50 TO 347+98.15 LT.		1		1.39			
STA. 347+98.15 TO 348+98.15 LT.			100	10.13	101		
STA. 348+98.15 TO 349+48.15 LT.	1			5.07			1
STA. 345+73.85 TO 349+48.15 LT.						5	
STA. 345+23.85 TO 345+73.85 RT.	1			5.07			1
STA. 345+73.85 TO 346+73.85 RT.			100	10.13	101		
STA. 346+73.85 TO 347+04.50 RT.		1		1.39			
STA. 347+67.50 TO 347+98.15 RT.		1		1.39			
STA. 347+98.15 TO 348+48.15 RT.			50	5.07	101		
STA. 348+48.15 TO 348+98.15 RT.	1			5.07			1
STA. 345+23.85 TO 348+98.15 RT.						5	
DIXON CREEK - TOTAL	4	4	300	56.24	404	10	4
TOTAL	8	8	550	107	808	19	8

PAVEMENT MARKING REMOVAL	
LOCATION	SQ FT
BRIDGE EDGE LINES ONLY	
LT. STA. 216+13.495 TO 216+76.50	21
WOLF CREEK - TOTAL	21
LT. STA. 347+04.50 TO 347+67.50	21
DIXON CREEK - TOTAL	21
TOTAL	42

RIPRAP SCHEDULE (ROADWAY)		
LOCATION	STONE RIPRAP, CLASS A4	FILTER FABRIC
	SQ YD	SQ YD
LT. STA. 215+50 TO 216+02	122.2	122.2
LT. STA. 216+85 TO 217+25	97.8	97.8
WOLF CREEK - TOTAL	220	220
LT. STA. 347+77.5 TO 351+00	645.0	645.0
DIXON CREEK - TOTAL	645.0	645.0
TOTAL*	865	865

*NOTE: FOR STRUCTURES QUANTITIES SEE BILL OF MATERIALS.

SHORT-TERM PAVEMENT MARKING		
LOCATION	FT	NO. OF APPLICATIONS
STA. 212+10 TO 219+40	73	3
WOLF CREEK - TOTAL	219	
STA. 307+06.65 TO 349+75	427	3
DIXON CREEK - TOTAL	1281	
TOTAL	1,500	

AGGREGATE DITCH CHECKS	
LOCATION	TONS
LT. STA. 215+50	17
LT. STA. 215+95	17
RT. STA. 216+86.5	17
LT. STA. 217+25	17
LT. & RT. STA. 218+00	34
WOLF CREEK - TOTAL	102
LT. & RT. STA. 343+00 TO 346+94.50	170
LT. & RT. STA. 347+77.50	34
LT. STA. 349+00	17
DIXON CREEK - TOTAL	221
TOTAL	323

AGGREGATE SHOULDERS, TYPE B	
LOCATION	TON
LT. & RT. - STA. 212+10 TO 213+00	25.4
LT. & RT. - STA. 218+00 TO 219+40	39.4
WOLF CREEK - TOTAL	64.8
LT. & RT. - STA. 307+06.65 TO 307+36.65	2.85
LT. & RT. - STA. 307+36.65 TO 313+59	59.12
LT. & RT. - STA. 313+59 TO 319+54.50	36.62
LT. & RT. - STA. 319+54.50 TO 341+85	211.9
LT. & RT. - STA. 341+85 TO 342+15	2.85
LT. & RT. - STA. 342+15 TO 343+25	31.0
LT. & RT. - STA. 349+75 TO 351+15	39.4
DIXON CREEK - TOTAL	324.6
TOTAL	389

CHANGEABLE MESSAGE SIGN	
LOCATION	CAL DA
STA. 210+10 TO 219+40	7
WOLF CREEK - TOTAL	7
STA. 342+15 TO 351+15	7
DIXON CREEK - TOTAL	7
TOTAL	14

WORK ZONE PAVEMENT MARKING REMOVAL				
LOCATION	COLOR	CONDITIONS	FOOT	SQ FT
WOLF CREEK - IL RTE. 94/116				
STA. 213+23.50 TO 219+66.50	WHITE	EAST & WEST EDGE	643	429
STA. 215+83.495 TO 217+06.505	WHITE	EAST EDGE	123	41
STA. 212+10 TO 219+40		SHORT-TERM PAVT MARK		24
WOLF CREEK - TOTAL				494
DIXON CREEK - IL RTE. 94				
STA. 344+14.50 TO 350+57.50	WHITE	EAST & WEST EDGE	643	429
STA. 345+74.50 TO 347+97.50	WHITE	EAST EDGE	223	74
STA. 307+06.65 TO 349+75		SHORT-TERM PAVT MARK		142
DIXON CREEK - TOTAL				645
TOTAL				1,139

MOWING	
LOCATION	UNIT
IL 94	49
TOTAL	49

PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	
LOCATION	EACH
75' LT. - STA. 350+95	1
DIXON CREEK - TOTAL	1
TOTAL	1