

EARTHWORK							
LOCATION	EARTH EXCAVATION	EARTH EX. ADJUST FOR SHRINKAGE	EMBANKMENT	(-) FURNISHED EX. / (+) WASTE	CHANNEL EXCAVATION	CHANNEL EX. ADJUST FOR SHRINKAGE	TOPSOIL EXCAVATION & PLACEMENT
	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
WOLF CREEK							
STA. 212+10 TO 213+00	2.96	2.22	61.67	-59.45			97
STA. 213+00 TO 214+00	58.33	43.75	237.04	-193.29			110
STA. 214+00 TO 215+00	83.33	62.50	398.15	-335.65			110
STA. 215+00 TO 216+26.75	164.82	123.62	676.00	-127.08	567	425.3	113.5
STA. 216+63.25 TO 217+00	268.34	201.26	70.78	+554.98	566	424.5	14.6
STA. 217+00 TO 218+00	1059.33	794.50	100.00	+694.50			110
STA. 218+00 TO 219+00	1924.07	693.05	9.26	+683.79			110
STA. 219+00 TO 219+40	417.04	312.78	2.22	+310.56			43
WOLF CREEK - TOTAL	3978.2	2233.7	1555.1	+1528.4	1133	849.8	708.1
DIXON CREEK							
STA. 342+00 TO 342+15	30.00	22.50	0.28	+22.22			16
STA. 342+15 TO 343+00	248.70	186.53	4.72	+181.81			94
STA. 343+00 TO 344+00	187.04	140.28	29.63	+110.65			111
STA. 344+00 TO 345+00	135.19	101.39	144.44	-43.05			111
STA. 345+00 TO 346+00	66.67	50.00	272.22	-222.22			111
STA. 346+00 TO 346+94.50	77.00	57.75	580.03	-109.78	550	412.50	105
STA. 347+77.50 TO 349+00	224.58	168.44	151.15	+429.04	549	411.75	137.1
STA. 349+00 TO 350+00	222.22	166.67	51.85	+114.82			111
STA. 350+00 TO 350+68	109.56	82.17	32.74	+49.43			75.5
STA. 350+68 TO 351+15	28.72	21.54	11.31	+10.23			52.1
DIXON CREEK - TOTAL	1329.7	997.3	1278.4	+543.2	1099	824.3	923.7
SUB-TOTAL	5307.9	3231.0	2833.5	2071.5	2232.0	1674.1	1631.8
TOTAL	5,310			+2075	2,235		1,635

EPOXY PAVEMENT MARKING - LINE 4"			
LOCATION	WHITE SOLID	YELLOW SOLID	YELLOW SKIP DASH
	FOOT	FOOT	FOOT
WOLF CREEK - IL RTE. 94/116			
STA. 212+10 TO 219+40	1460		190
STA. 212+10 TO 213+75		165	
WOLF CREEK - TOTAL	1460	165	190
DIXON CREEK - IL RTE. 94			
STA. 307+06.65 TO 321+00	2787	2787	
STA. 321+00 TO 332+00	2200	1100	275
STA. 332+00 TO 342+00	2000	1000	250
STA. 342+00 TO 342+15	30	30	
STA. 342+15 TO 351+15	1800		230
STA. 342+15 TO 342+50		35	
DIXON CREEK - TOTAL	8817	4952	755
SUB-TOTAL	10,277	5,117	945
TOTAL	16,339		

AGGREGATE SURFACE COURSE, TYPE B	
LOCATION	TON
STA. 214+62 - ENTRANCE	106.4
WOLF CREEK - TOTAL	106.4
STA. 344+30 - ENTRANCE	81.9
STA. 351+00 - ENTRANCE	61.1
DIXON CREEK - TOTAL	143
TOTAL	249

LOCATION	MULCH METHOD 2	SEEDING, CL 2	SEEDING, CL 3	TEMPORARY EROSION CONTROL SEEDING	FERTILIZER*		
	ACRE	ACRE	ACRE	POUND	NITROGEN POUND	PHOSPHORUS POUND	POTASSIUM POUND
WOLF CREEK							
STA. 212+10 TO 216+13.495 LT & RT	1.25	0.50	1.00	450	120	120	120
STA. 216+76.505 TO 219+40 LT & RT							
WOLF CREEK - TOTAL	1.25	0.50	1.00	450	120	120	120
DIXON CREEK							
STA. 342+15 TO 347+04.50 LT & RT	1.50	0.50	1.50	525	157	157	157
STA. 347+67.50 TO 351+15 LT & RT							
DIXON CREEK - TOTAL	1.50	0.50	1.50	525	157	157	157
TOTAL	2.75	1.00	2.50	975	277	277	277

*FERTILIZER APPLICATION RATE 90 LB/ACRE

BRIDGE APPROACH PAVEMENT	
LOCATION	SQ YD
STA. 216+13.50 TO 216+76.50	222.2
WOLF CREEK - TOTAL	222.2
STA. 347+05.75 TO 347+67.50	222.2
DIXON CREEK - TOTAL	222.2
TOTAL	444

PERIMETER EROSION BARRIER	
LOCATION	FOOT
WOLF CREEK	3560
DIXON CREEK	3672
TOTAL	7,232

TEMPORARY PAVEMENT MARKING				
LOCATION	4"			**24"
	COLOR	CONDITIONS	FOOT	FOOT
WOLF CREEK - IL RTE. 94/116				
*STA. 213+23.50 TO 219+66.50 PHASE I	WHITE	EAST & WEST EDGE	1286	24
*STA. 213+23.50 TO 219+66.50 PHASE II	WHITE	EAST & WEST EDGE	1286	24
WOLF CREEK - TOTAL			2572	48
DIXON CREEK - IL RTE. 94				
*STA. 344+14.50 TO 350+57.50 PHASE I	WHITE	EAST & WEST EDGE	1286	24
*STA. 344+14.50 TO 350+57.50 PHASE II	WHITE	EAST & WEST EDGE	1286	24
DIXON CREEK - TOTAL			2572	48
TOTAL			5,144	96

*STOP BAR TO STOP BAR @ STD 701321

** 2 STOP BARS PER PHASE

MATERIAL TRANSFER DEVICE	
LOCATION	TON
WOLF CREEK	
HMA SURFACE CSE	187
HMA BINDER CSE	575
HMA SHOULDERS	187
DIXON CREEK	
HMA SURFACE CSE	1097
HMA BINDER CSE	726
HMA SHOULDERS	271
TOTAL	3,043