

URBAN

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	0011 PEORIA S.N. 072-0001 90 FED/10 ST	0011 PEORIA S.N. 072-0002 90 FED/10 ST	0004 PEORIA ROADWAY 90 FED/10 ST	0004 PEORIA MOWING 100 ST
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6			6	
67100100	MOBILIZATION	L SUM	1			1	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1			1	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1			1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20			20	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	320			320	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	65,227			65,227	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	107			107	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2,700			2,700	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	2,700			2,700	
70500100	TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	25			25	
70500615	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	2			2	
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	7,451			7,451	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	125			125	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	19,826			19,826	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	125			125	
80300100	LOCATING UNDERGROUND CABLE	FOOT	1,200			1,200	
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA, PVC	FOOT	157			157	
81300835	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" X 18" X 10"	EACH	2			2	
X0323357	CONCRETE BARRIER REMOVAL AND REPLACEMENT	FOOT	360			360	
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	496	248	248		

*SPECIALTY ITEM

FILE NAME = D468874-topo.dgn

USER NAME = johnsantv

DESIGNED -

REVISED -

DRAWN -

REVISED -

CHECKED -

REVISED -

DATE -

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE:

SHEET NO. 4 OF 5 SHEETS

STA.

TO STA.

F.A.I. RTE.

74

SECTION

72(6VBIBY)

COUNTY

PEORIA

TOTAL SHEETS

133

SHEET NO.

7

CONTRACT NO. 68874

ILLINOIS FED. AID PROJECT