

EROSION CONTROL SCHEDULE									
LOCATION	TEMPORARY DITCH CHECKS		TEMPORARY EROSION CONTROL SEEDING	SEEDING, CLASS 2A	EROSION CONTROL BLANKET	MULCH, METHOD 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT
	FT		POUND	ACRE	SQ YD	ACRE	POUND	POUND	POUND
	DURING STAGING	X-OVER REMOVAL	100 LB/ACRE				90 LB/ACRE	90 LB/ACRE	90 LB/ACRE
I-74 MAINLINE									
STA. 335+00 TO STA. 335+50	43	43	11.02	0.06	55.56	0.06	4.96	4.96	4.96
STA. 335+50 TO STA. 336+00			11.02	0.06	55.56	0.06	4.96	4.96	4.96
STA. 336+00 TO STA. 336+50			11.02	0.06	55.56	0.06	4.96	4.96	4.96
STA. 336+50 TO STA. 337+00	27	46	11.02	0.06	55.56	0.06	4.96	4.96	4.96
STA. 337+00 TO STA. 337+50			11.02	0.06	55.56	0.06	4.96	4.96	4.96
STA. 337+50 TO STA. 338+00			11.02	0.06	55.56	0.06	4.96	4.96	4.96
STA. 338+00 TO STA. 338+50	46	46	11.02	0.06	55.56	0.06	4.96	4.96	4.96
STA. 338+50 TO STA. 339+00			11.02	0.06	55.56	0.06	4.96	4.96	4.96
STA. 339+00 TO STA. 339+50			11.02	0.06	55.56	0.06	4.96	4.96	4.96
STA. 339+50 TO STA. 340+00	47	46	11.02	0.06	55.56	0.06	4.96	4.96	4.96
STA. 340+00 TO STA. 340+50			11.02	0.06	55.56	0.06	4.96	4.96	4.96
STA. 340+50 TO STA. 341+00			11.02	0.06	55.56	0.06	4.96	4.96	4.96
STA. 341+00 TO STA. 341+50	26	48	11.02	0.06	55.56	0.06	4.96	4.96	4.96
STA. 341+50 TO STA. 342+00			11.02	0.06	55.56	0.06	4.96	4.96	4.96
STA. 342+00 TO STA. 342+50			11.02	0.06	166.67	0.06	4.96	4.96	4.96
STA. 342+50 TO STA. 343+00	42	48	11.02	0.06	55.56	0.06	4.96	4.96	4.96
STA. 343+00 TO STA. 343+50			11.02	0.06	55.56	0.06	4.96	4.96	4.96
STA. 343+50 TO STA. 344+00			11.02	0.06	55.56	0.06	4.96	4.96	4.96
STA. 344+00 TO STA. 344+50	52	50	11.02	0.06	55.56	0.06	4.96	4.96	4.96
STA. 344+50 TO STA. 345+00			11.02	0.06	55.56	0.06	4.96	4.96	4.96
STA. 345+00 TO STA. 345+50			11.02	0.06	55.56	0.06	4.96	4.96	4.96
SUB-TOTAL	245	328	231.40	1.16	1,277.78	1.16	104.13	104.13	104.13
TOTAL	573		250	1.25	1,278	1.25	105	105	105

TRAFFIC CONTROL AND PROTECTION			
LOCATION	STD. 701406	STD. 701411	(SPECIAL)
	L SUM	EACH	LSUM
I-74 CROSS-OVER	1	1	1
TOTAL	1	1	1

SCHEDULE OF TEMPORARY CONCRETE BARRIER QUANTITIES		
LOCATION	TEMP. CONCRETE BARRIER	RELOCATE TEMP. CONCRETE BARRIER
STAGE I	2,700	
STAGE II		2,700
TOTAL	2,700	2,700

INLET AND PIPE PROTECTION	
LOCATION	EACH
I-74	
STA. 333+01.77	1
STA. 337+50.00	1
STA. 341+50.00	1
STA. 344+77.71	1
STA. 345+92.03	1
STA. 345+99.64	1
TOTAL	6

BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	
LOCATION	SQ YD
S.N. 072-0001 EB	54.67
S.N. 072-0002 WB	54.67
TOTAL	110

TRAFFIC CONTROL SURVEILLANCE	
LOCATION	CAL DA
I-74 CROSS OVERS	20
TOTAL	20