

LOCATION OF WORK:	US 136	US 136
	RURAL TWO LANE	RURAL TWO LANE
	BRIDGE REPLACEMENT	BRIDGE REPLACEMENT
	MCLEAN COUNTY	MCLEAN COUNTY
	STA. 415+00 TO STA 442+00	STA. 415+00 TO STA 442+00
	OVER KICKAPOO CREEK	OVER KICKAPOO CREEK
	1.3 MIW OF U.S. 51	1.3 MIW OF U.S. 51

FUNDING BREAKOUT:	80% FEDERAL / 20% STATE	80% FEDERAL / 20% STATE
CONSTRUCTION TYPE CODE:	0004	0011

CODE NO.	ITEM	UNIT	ROADWAY QUANTITY	BRIDGE QUANTITY	TOTAL QUANTITY
50300260	BRIDGE DECK GROOVING	SQ YD	0.0	1,401.0	1,401.0
50300280	CONCRETE ENCASEMENT	CU YD	0.0	19.8	19.8
50300300	PROTECTIVE COAT	SQ YD	0.0	1,773.0	1,773.0
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	0.0	1.0	1.0
50500505	STUD SHEAR CONNECTORS	EACH	0.0	8,406.0	8,406.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	0.0	147,390.0	147,390.0
50800515	BAR SPLICERS	EACH	0.0	1,368.0	1,368.0
51200950	FURNISHING METAL SHELL PILES 14" X 0.312"	FOOT	0.0	810.0	810.0
51201800	FURNISHING STEEL PILES HP14X73	FOOT	0.0	2,699.0	2,699.0
51202305	DRIVING PILES	FOOT	0.0	2,699.0	2,699.0
51203200	TEST PILE METAL SHELLS	EACH	0.0	2.0	2.0
51203800	TEST PILE STEEL HP14X73	EACH	0.0	4.0	4.0
51500100	NAME PLATES	EACH	0.0	1.0	1.0
52100520	ANCHOR BOLTS, 1"	EACH	0.0	48.0	48.0
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	1.0	0.0	1.0
54001002	BOX CULVERT END SECTIONS, CULVERT NO. 2	EACH	1.0	0.0	1.0
54001061	GRATED BOX CULVERT END SECTIONS, CULVERT NO. 01	EACH	1.0	0.0	1.0
54001062	GRATED BOX CULVERT END SECTIONS, CULVERT NO. 02	EACH	1.0	0.0	1.0
54010503	PRECAST CONCRETE BOX CULVERTS 5' X 3'	FOOT	40.0	0.0	40.0
54020706	PRECAST CONCRETE BOX CULVERTS 7' X 6' (M273)	FOOT	48.0	0.0	48.0
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1.0	0.0	1.0

* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = hagenbj	DESIGNED - BJH 7/12/2011	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\hagenbj\0142533\057052-sht-500.dgn	DRAWN -	REVISOR -	315					121BR-2	MCLEAN	144	8	
PLOT SCALE = 100.0000 / in.	CHECKED -	REVISOR -	SCALE: _____ SHEET NO. 3 OF 6 SHEETS STA. _____ TO STA. _____			CONTRACT NO. 70552						
PLOT DATE = 8/22/2011	DATE -	REVISOR -	[ILLINOIS] FED. AID PROJECT									